

4-27-2E


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
503 East Murdock, Wichita, Kansas

Company- W. L. HARTMAN
Farm- Rowland No. 2

SEC. 4 T. 27 R. 2E
CN/2 NW SW

Total Depth. 3465
Comm. 6-26-53 Comp. 7-11-53
Shot or Treated.
Contractor. Morrison Drlg. Co., Inc.
Issued. 8-1-53

County Sedgwick
KANSAS



CASING:

8" 103'

Elevation. 1416

Production. SWD/W

Figures indicate Bottom of Formations.

cement	103
shale	140
lime w/shale brks	215
lime	360
lime & shale strks	465
shale & shells	560
lime & shale	620
red bed	630
shale & lime	635
lime & shale strks	740
lime	950
lime & shale	1065
shale & shells	1250
shale & lime	1360
shale & lime strks	1525
lime w/shale brks	1550
lime & shale	1930
lime w/shale strks	2025
lime & shale	2160
lime	2390
lime w/shale strks	2430
shale w/lime brks	2520
lime K. C.	2685
shale & lime strks	2728
lime & shale	2890
shale & lime strks	2945
Core #1	2960
Core #2	2975
Core #3	2990
Core #4	2996
lime & shale strks	3060
lime, cherty	3115
lime	3255
lime w/shale strks	3295
dolomite	3330
lime	3338
sand, Simpson	3390
shale & sand	3419
lime	3465
Total Depth	

Scout Tops:	
Heebner	1947
Lansing	2159
Kansas City	2518
Marmaton	2680
Miss. Lime	2988
Miss. Lime	3010
Kinderhook	3243
Misener	3295
Hunton	3296
Viola	3317
Simpson	3333
Arbuckle	3418