

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY
412 Union National Bk Bldg., Wichita, Kansas

MAGNOLIA PETRO.CO.
A. Jabs No. 1.

SEC. 8 T. 27 R. 2E
NE NW SE

Total Depth. 3310'
Comm. 8-25-38 Comp. 9-28-38
Shot or Treated.
Contractor.
Issued. 11-19-38

County. Sedgwick



CASING:
13" 116'
8 5/8" 2969'
7" 3254'

Elevation.

Production. Dry

Figures Indicate Bottom of Formations.

lime & shale	250	1000' salt wtr & 0 oil 2984-86
lime	508	Dry hole 3254- 3282
shale & lime shells	545	Picked up approx. 200' of wtr at 3282
lime	845	Firm Misener sand - no oil - water
lime & shale	1085	gradually increased and at 3310
shale	1242	hole approx. full of water.
lime & shale	1325	
shale	1425	Plugged & Abnd.
lime	1495	
shale & lime	1765	
lime	1818	
shale	1828	
lime	1980	
lime & shells	2012	
shale & lime	2105	
shale & shells	2132	
lime	2152	
shale	2186	
lime hrd	2220	
lime sft	2318	
lime hrd	2343	
lime	2383	
shale hrd	2423	
shale & shells	2500	
Top Kansas City lime	2500	
Kansas City lime	2672	
Kansas City lime sft 2570-85		
Kansas City lime firm 2585-90		
Kansas City lime hrd 2610-33		
lime & shale	2680	
shale	2727	
lime	2745	
shale	2755	
lime	2785	
shale red	2790	
lime	2824	
lime & shale	2957	
shale Top Chat 2967	2967	
chat	2970	
Standardized		
shale blue	2984	
dry from 2969-2984		
chat white hrd	2984	
chat	3060	
lime hrd	3076	
lime	3174	
shale green	3180	
shale green	3197	
lime	3225	
shale blk	3235	
shale (Top Misener sand	3279	
Misener sand 3279)	3280	
Misener dolomite	3300	
Top Viola dolomite	3300	
Viola dolomite	3310	
Total Depth.		