


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- J. P. GATY
 Farm- Hoult No. 6

SEC. 14 T. 27 R. 2E
 SE SW NE

Total Depth. 3260'
 Comm. 5-17-54 Comp. 5-26-54
 Shot or Treated.
 Contractor. Morrison Drlg. Co., Inc.
 Issued. 8-7-54

County Sedgwick
 KANSAS



CASING:
 8" 54'
 5 1/2" 3238

Elevation. 1323'

Production. Pmp 25 & 10% wtr.

Figures indicate Bottom of Formations.

cement	75
lime	205
lime and shale	575
shale & lime streaks	685
lime and shale	730
shale & lime streaks	950
lime and shale	1185
shale and lime	1450
lime and shale	1500
shale and lime	1530
lime and shale	1630
lime & shale streaks	1650
gummy shale	1710
lime & shale	2160
shale and lime	2379
lime - Kansas City	2445
lime	2585
lime & shale streaks	2640
lime and shale	2745
lime and shale	2836
lime - Mississippi	2905
lime and chert	3035
lime - Mississippi	3057
lime and shale	3088
shale	3129
lime	3161
Simpson Sand	3233
Arbuckle Sand	3238 RTD
Arbuckle	3260 CTTD
Total Depth	

Tops:	Scout	
Kansas City	"	2378
Marmaton	"	2557
Mississippi	"	2838
Kinderhook	"	3078
Hunton	"	3129
Viola	"	3142
Arbuckle		3235

T. Arb. 3235. Casing landed 3238
 Deepened to 3260. Ran ordinary squeeze
 job by Halliburton and squeezed all of
 open hole. Drilled out cement to 3241.
 Perforated 3238-40 1/2 with 10 Dowell jet
 shots, and then acidized with 125 gal.
 Swabbed 2.92 BO/H plus 32% water.