

19-~~12~~ 25  
By *Amelia*

UNION NATIONAL BANK BLDG, WICHITA, KANSAS

DEC 26 1931

Location SW SE NE.

DEPARTING RECORD.

Sec. 19 T. 27 R. 2E.

330' fr SL 1378' fr WL NE/4

Casing Record


County- Sedgwick.

20" 10" 2955'  
15 1/2" 53'6 65/8" 3201  
12 1/2" 53/16"

Farm- Eastborough  
Company- Derby Oil Co.  
Contr.- McPherson Drlg. Co.  
Comm.- 8/30/30. Comp. 11-25-31

Total Depth 3226 Shot Quarts Between

Correspondence Regarding This Well Should Be Referred to



Elevation 1360

Figures Indicate Bottom of Formations.

Initial Production

Date Issued.

Swabbed 45 bbls per hr.

12/26/1931.

Formation	Depth	Formation	Depth
surface	20	shale	1695
clay	43	lime	1720
sand	48	shale	1800
shale	51	lime	1912
lime	55	shale	1965
brkn lime	180	lime	1975
lime	205	shale	2025
brkn lime	410	brkn lime	2045
shale	430	shale	2065
brkn lime	540	shale	2080
shale	560	lime	2105
brkn lime	600	shale	2165
shale	610	brkn lime	2245
lime	620	shale	2295
brkn lime	700	lime	2690
shale	725	shale	2895
brkn lime	735	brkn lime	2925
shale	790	shale	2930
brkn lime	810	red rock	2935
shale	855	shale	2954
lime	875	chat	2955
shale	890	Steel line of Rotary Drill pipe	
brkn lime	935	2955' SLM equals 2957'	
shale	960	Standardized	
brkn lime	1000	Measurement on sand line strung	
shale	1040	over Derrick 2955 Rotary equals	
brkn lime	1070	2949 Standard.	
shale	1095	49' of cement plug.	
lime	1135	chat brown	2953
shale	1235	red rock	2955
lime	1250	chat brown & varigated	
shale	1285	shales	2958
brkn lime	1305	varigated shales	2974
shale	1390	Free oil & gas	
brkn lime	1420	chat white sft	2984
shale	1460	No increase	
brkn lime	1475	chat white mod	2988
shale	1500	no increase	
brkn lime	1545	chat white mod.	2991
shale	1560	Increase in oil	
lime	1590	Swabbed 45 bbls per hr.	
shale	1625	chat white sft	2993 ...
brkn lime	1650	Increase in oil	
		1st 12 hrs swabbed 650 bbls.	
		1st 24 hrs swabbed 1350 bbls.	
		chat	3081
		lime	3125
		shale green	3152
		lime	3176
		shale blk	3231
		dolomite soft	3233 Oil
		dolomite soft inc in oil	3235
		dolomite hard	3236
		swabbed 4 1/2 bbper hr.	
		dolomite mod	3237
		shale grey	3239
		3239 equals 3241 S.L.M.	
		Viola lime	3246 TD.

slight inc in oil 3241.  
Hole full oil