

UNION NATIONAL BANK BLDG WICHITA KANSAS

Location SE NW NE NE. DEEPENING RECORD.

Sec. 19 T.27 R. 2E.

1758' of EL 653' of NL NE/4

Casing Record

County- Sedgwick.

10" 1585 Farm- Eastborough No. 3


20" 8" 2629 Company- Derby Oil Company.

15 1/2" 62 65/8" 2962 Contr.- Greenwich Drilling Co.

12 1/2" 865 53/16" 3245 Comm.- 9/19/30. Comp.-12-20-31

Total Depth 3280 1/2 Shot Quarts Between

Correspondence Regarding This Well Should Be Referred to



Elevation

Figures Indicate Bottom of Formations.

Initial Production

Date Issued. 1-9-32

800 bbls.

Formation	Depth	Formation	Depth	Formation	Depth.
clay yellow	23	lime	1610	chat wh	3073
shell	26	Bailing hole dry		lime white	3130
shale blue	49	shale	1639	shale green	3140
lime water	55	lime	1650	lime white	3164
shale	80	shale	1697	shale blue	3180
lime	103	lime	1750	lime white	3215
shale	118	lime	1756	slate grey	3245
lime	130	shale	1763	shale dark grey	3267
shale	145	lime 3 BW 1865'	1855	top of Misner	3267
lime	171	lime	1983	hole caving	3230-45
shale	173	shale	1989	lime brown	3272
lime	282	lime	2003	UR 53/16	3266
shale	318	shale	2160	top cement plug	3235
lime	474	lime	2168	shale grey	3279 1/2
Corrected to	454	shale	2192	lime viola	3280 1/2
lime	520	lime	2225	TD.	
shale	529	lime & shale	2275		
lime	540	shale	2322		
shale	551	lime	2341		
lime	605	shale	2503		
shale & red rock	618	lime	2588		
shale	645	lime 8 BW 2597	2614		
lime	705	lime Brake	2685		
shale	726	shale	2722		
lime	760	shale blue	2730		
shale	766	shale white	2762		
lime	828	Bailing hole dry.			
shale	833	red rock	2780		
lime	840	shale	2790		
shale	845	lime	2795		
lime 3 BW	850	shale	2805		
lime	865	lime	2845		
shale	870	shale	2851		
lime	920	lime	2859		
shale	928	shale	2863		
lime	945	lime	2870		
shale	955	shale	2887		
lime	979	lime	2899		
shale	1129	shale	2903		
lime	1131	lime	2907		
shale	1145	shale	2913		
lime	1185	lime	2930		
2 BW 1152'		shale	2947		
lime 12 BW	1197	red rock	2950		
shale	1222	shale	2955		
lime	1256	chat brown	2957		
shale	1263	vari-colored shale	2966		
lime	1288	lime white	2971		
shale	1295	sdv lime drk	2975		
lime	1305	shale green	2976		
shale	1310	chat sft white	2977		
lime	1328	1st oil & gas filled up			
shale	1400	1500' in 40 min.			
brkn lime	1420	chat sft white	2979 1/2	No Increase.	
lime	1463	chat sft white	2981 1/2	Increase in oil	2150'
shale	1469	chat sft white	2987	of fluid.	
lime	1475				
shale	1480				
lime	1500				
shale	1542				

plst.