

UNION NATIONAL BANK BLDG., WICHITA, KANSAS.

Location NE cor S¹/₄ SE¹/₄ DEEPENING RECORD.

Sec. 19 T. 27 R. 2E.

Casing Record

County- Sedgwick.

10" 1556 Farm- Trustee No. 1
 20" 8" 2700 Company- Fisher & Lauck
 15 1/2" 62 65/8" 2927 Contr.- Fisher & Lauck.
 12 1/2" 896 53/16" Comma.- 10/29/1929. Comp.- 12/3/1929.
 Total Depth 3244 Shot Quarts Between
 Correspondence Regarding This Well Should Be Referred to



Figures Indicate Bottom of Formations.
 Date Issued. 3-19-32

Initial Production 6 bbls per hr.

Formation	Depth	Formation	Depth	Formation	Depth
clay yellow	32	brkn lime	873	lime	1917
slate blue	53	lime hrd	878	lime grey hrd	1945
lime grey	62	lime shells	900	slate grey sft	1955
slate blue	75	lime hrd	905	lime grey hrd	1965
lime grey	97	shale lgt	965	sl to grey sft	1985
sl to lgt	100	sl to blue	973	slate drk	1996
lime brown	109	lime	977	slate blk	2000
slate blue	114	sl to blue	1005	lime	2020
lime white	130	lime	1010	sdv shale	2030
slate blue	135	sl to lgt	1035	sdv shale	2070
lime & shale	150	lime brown hrd	1040	brkn lime sft	2085
lime grey	170	slate lgt sft	1085	sdv shale sft	2130
sl to blue	175	sl to blue	1106	lime white hrd	2170
lime grey	190	lime	1110	lime white hrd	2200
slate blue	203	sl to blue	1142	sl to grey sft	2205
lime grey	212	lime	1150	slate blue	2235
slate blue	217	slate blue	1165	slate blue	2250
lime grey Gas	220	lime	1169	lime grey hrd	2255
shale blue	225	slate	1185	slate blue sft	2285
lime brown	230	lime grey hrd	1190	lime grey hrd	2300
lime grey	234	slate blue sft	1200	slate lgt	2310
slate	240	lime brown hrd	1210	slate blue	2334
lime	250	slate blue sft	1240	sl to blue sft	2390
slate blue	255	sl to blue	1245	lime grey hrd	2395
lime white hrd	260	lime shells	1255	slate blk sft	2405
slate lgt sft	275	lime shells	1260	lime grey hrd	2410
lime grey hrd	285	sl to blue	1275	slate blk sft	2415
slate blue sft	295	1/2 BW 1288		sl to blk	2425
lime grey hrd	300	lime brown hrd	1293	sl to blue	2435
slate blue sft	305	sl to blue	1310	sl to lgt KC	2452
slate blue	310	slate blue 6 BW	1380	lime	2463
lime sdv grey	400	lime sdv	1385	lime grey hrd	2466
lime grey	450	lime grey hrd	1430	slate grey sft	2475
brkn lime brown	475	lime	1433	lime grey hrd	2498
sl to blue-lm shale	550	sl to	1435	lime brown hrd	2510
lime grey hrd 1/2 BW	575	lime	1436	lime grey sharp	
sl to blue	578	slate	1440	hrd	2540
red rock	587	lime 6 BW	1475	lime grey sharp	2560
lime grey	595	sdv shale grey	1520	6 BW 2550-2601	
shale & shells	610	lime grey hrd	1530	lime sharp hrd	2580
lime grey hrd	657	lime grey hrd	1545	slate black	2582
red rock	660	3 BW 1550		lime grey hrd	2600
lime grey hrd	680	sdv lime	1553	lime grey hrd	2625
slate blue	685	lime grey hrd	1560	lime drk grey	2645
lime grey hrd	705	lime brown hrd	1565	shale blk	2690
slate blue	710	slate grey sft	1605	slate lgt	2697
lime grey hrd	745	lime grey hrd	1610	lime	2700
lime	750	lime grey hrd	1620	lime grey hrd	2712
lime grey hrd	760	sl to blue	1625	sl to lgt green	2730
sl to lgt	762	lime grey hrd	1635	lime grey	2745
lime	778	slate blue	1640	slate lgt green	2747
sl to blue	781	lime grey hrd	1645	lime grey hrd	2752
slate blk	786	slate white	1651	red rock sft	2755
lime hrd	790	lime grey hrd	1660	sl to grey sft	2775
slate blue	793	slate white sft	1710	lime grey hrd	2780
lime	805	lime grey hrd	1715	sl to grey sft	2785
slate	815	sl to grey sft	1730	sl to lgt	2800
lime grey hrd	825	lime grey hrd	1735	lime	2808
slate black sft	830	lime grey hrd	1850	sl to blk	2814
lime brown hrd	848	1/2 BW 1810'		lime	2820
slate grey	850	lime	1901	red rock	2825
sdv lime	860	slate blk	1904	shale & shells	2877

(OVER)

Section 19-27-2E.
Trustee Number 1: NE 1/4 Sec 6E

Formation	Depth.
slate and shells	2902
red rock	2913
shale yellow	2918
shale	2927
chat hard	2929
chat soft oil	2937
lime hard white	2938
T.D.	

OLD TOTAL DEPTH 2938

DEEPENING RECORD.

COMMENCED- 2-19-32 COMPLETED- 3-13-32

PRODUCTION- 25 bbls per hour on pump well not swabbed.

Formation	Depth.
lime	2974
lime grey	2989
lime	3012
lime sdy	3035
lime sdy	3055
lime sdy	3090
lime sdy	3097
red rock	3103
lime	3118
lime hard	3125
shale green	3137
shale green	3146
lime	3183
shale blk	3207
shale blk	3212
lime	3215 set 53/16
shale blk	3235
sand Oil	3244
T.D.	

Plot.