

OILFIELD RESEARCH LABORATORIES

536 NORTH HIGHLAND - CHANUTE, KANSAS 66720 - PHONE (316) 431-2650

October 8, 1980

KLI Petroleum Corporation
Evans Construction Company
P.O. Box 1159
Henderson, Kentucky 42420

Gentlemen:


Attached hereto are the results of tests run on the rotary core taken from the Elmer Lease, Well No. K-5, located in Allen County, Kansas.

The core was sampled and sealed in plastic bags by a representative of the client and submitted to our laboratory on October 2, 1980.

Your business is greatly appreciated.

Very truly yours,

OILFIELD RESEARCH LABORATORIES


Sanford A. Michel

SAM/tem

5 c to Henderson, Kentucky

T 27S, R 22E, Sec. 30

- REGISTERED ENGINEERS -

CORE ANALYSIS - WATER ANALYSIS - REPRESSURING ENGINEERING - SURVEYING & MAPPING - PROPERTY EVALUATION & OPERATION

OILFIELD RESEARCH LABORATORIES

LOG

Name KLI Petroleum Corporation Lease Elmer Well No. K-5

Depth Interval,
Feet

Description

TUCKER SAND

570.0 - 573.2

Light brown sandstone.

573.2 - 578.0

Brown and gray laminated sandstone
and shale.

Oilfield Research Laboratories
RESULTS OF PERMEABILITY AND POROSITY TESTS
TABLE I A

Company KLI Petroleum Corp. Lease Elmer Well No. K-5

Sample No.	Depth Feet	Permeability Millidarcys	Feet of Core		Permeability Capacity Ft. x Md.	Percent Porosity
			Ft.	Cum. Ft.		
1	570.5	121.				27.8
2	571.5	65.				26.8
3	572.5	12.				22.9
4	573.5	1.0				16.2
5	574.5	2.2				17.7
6	575.5	2.2				18.2
7	576.5	2.3				16.8
8	577.5	0.39				15.0