

# SU CLIFF PIPE & SUPPLY BRILLINA

JOE SUTCLIFFE

PHONE 1844 CHANUTE  
PHONE Temple 8-3601 WICHITA

119 S. GRANT, CHANUTE, KANSAS  
5708 N. BROADWAY, WICHITA, KANSAS

## Well Record

COMPLETE LINE OF NEW & USED PIPE - BELTING - STORAGE TANKS, WIRE LINES

Well No. 1	Farm Ward	Producer Tom Bird
Location	Sec. 15	Twp. 27S Rg. 22E
Elevation	State Kansas	County Bourbon
Kind (Oil, Gas, Water, Dry Hole) Dry Hole	Contractor Sutcliffe Pipe & Supply	
Producing formation	Top	Bottom
Shot with	qts.	from to
Packer set at	Kind Rag Packer	Size
Liner	from to	Perforated from to

### LOG

Thickness	Strata	Depth	Thickness	Strata	Depth
6	Soil & clay	6	30	Dark sdy shale	35
14	Shale	20	10	Miss chat	645
6	Shale	26			
29	Lime & Shale	55			
73	Sand & Shale	128			
46	Lime (40')	174			
30	Shale	204			
23	Sdy. Sh.	227			
18	Lime (20')	245			
7	Shale	252			
13	Lime (5')	265			
15	Sd w/lite show				
	oil	280			
50	Sdy shale	330			
41	Dark Shale	371			
2	Lime	373			
47	Sh. to Sdy Sh.	420			
45	Sdy Shale	465			
10	Sable w/ ls.				
	shells	475			
25	Dark shale	500			
22	Sdy Shale	522			
2	Soft white shale	524			
4	Sdy Shale	528			
3	Sand & No oil show	531			
14	Sdy Shale	545			
9	Dark Shale	554			
24	Lite Sandy shale	578			
20	Dark Shale	598			
7	Lite sdy shale	605			

Total Depth

Open Hole

Casing 21' of 7" at Surface

Casing at

Casing at

Cement

Tubing

Rods

Additional Information

Make 3 sack rag packer on surface pipe

Car for samples 516' to 551' & 593' to 645'.

Run drill pipe to 140' & spot

8 sacks cement, pull drill pipe &

pour 2 sacks dry cement with packer

in surface pipe.

Date Completed Dec. 22, 1961

O.K.

Superintendent

Started Dec. 20, 1961

606

# OFFICE COPY

## SCOUT REPORT

COMPANY: BIRD

FARM: WORD

Drilled: 1962

NW NW

Sec. 15-27S-22E

Bourbon Co., Kansas

Elevation: 970'

Ft. Scott	228
Squirrel sand	264 - 275 Light S.O.
Miss. Chert	635
TOTAL DEPTH	645
Drill Stem #1	
Miss. 638 - 645	300,000 Cu. ft/gas