

Company Brazil et al

18-27-22E
Sec. 18 T. 27 R. 21
Loc. SE Cor SE 1/4
County Bourbon

Farm Schooley

No. 1

Total Depth 764

Comm. 8-17-53

Comp. 9-19-53

Shot or Treated-Completed gas well

Contractor Elmer Abercrombie Jr.

Issued



Casing

20 in.	10 in
15 1/2	8 1/4
12 1/2	6 5/8 --430
13 3/8	5 3/16

Elevation

Production

Figures Indicate Bottom of Formation

2	soil	2
18	lime	20
165	shale	185
17	lime	202
4	shale	206
4	lime	210
20	shale	230
20	sand	250--water
15	shale	265
39	lime	304
2	shale	306
9	lime	315
35	shale	350
5	lime	355
5	sand	360
7	shale	367
20	lime	387
7	shale black	394
6	lime	400
5	shale	405
15	sand	420
10	shale	430--6-1/4"
100	shale	530
10	sand-shale	540
10	shale gray	550
40	shale	590
10	sand-shale	600
10	shale black	610
14	sand	624
76	shale	700
28.5	shale black	728.5
26.1	sand black-gas	754.6--gas at top of sand
6.4	shale & sand	761
2	sand black	763
1	sand-shale	764

Mr. Geo. Babcock
discovered this location
to 27^s-22^E SEP.