

op	Bottom	LOG Formation and Remarks	State Kansas
3	3	Soil	County Bourbon
26	29	Lime	Sec 8 Twp 27 Range 24
18	47	Shale Dark	Farm Perry Well No. 1
2	49	Lime reduced hole from 10"	SE Corner NW 1/4 8-27-24
16	66	Shale Dark to 8 1/2 @ 81 ft.	Company Millsap Oil and Gas Company
3	87	Lime	
18	88	Shale Light	
5	90	Shale Dark	Contractor Pittman Drilling Company, Inc.
14	104	Lime	
7	111	Shale dark	
6	117	Lime	Commenced 8-11-55
8	125	Shale dark little water	
13	140	Shale Light	Completed 6-16-55
40	180	Shale Dark	
16	196	Shale Light	Casing Record
1	197	Lime	8' 10" Casing
5	202	Shale Dark	
4	206	Lime	
9	215	Shale Light	
4	219	Lime 140 ft. water over night	
6	223	Shale Black	
7	232	Shale dark	
6	238	Shale Light	
9	247	Dark Shale	
13	262	Shale Light	
10	272	Sand	
14	286	Shale dark	
1	287	Lime	
8	295	Shale dark	
9	304	Shale Light	
5	309	Sand	
5	314	Shale Light	
1	315	Red mud	
4	319	Sand	
13	332	Shale Light	
15	347	Shale dark	
6	353	Sand gray - dry--no show or smell	
4	357	Shale	
2	359	Lime	
61	420	Shale Light Light and little sandy	
41	461	Shale Dark 300 ft. water over Sunday	
11	472	Sand Oil Steel Line Measure at 466 1/2 ft.	
3	473	Shale	
3	478	Coal	
2	480	Shale	
34	514	Lime chat Mississippi	
6	520 TD	Lime Hard	