

Company J. N. Knapp

Sec. 24 T. 27 R. 17E

Farm Dearborn

No. 1

Loc.

County Neosho


Total Depth 860
Comm. Feb. 18, 1903

Comp.

Shot or Treated

Contractor Drilled by owner

Issued



Elevation 740

Production

Casing	
20 in.	10 in
15 1/2	8 1/4
12 1/2	6 5/8
13 3/8	5 3/16
8 3/4	17'
6 1/2	298'
5"	665'
2"	842'

Figures Indicate Bottom of Formation

Soil	3
Limestone	23
Sand	31
Shale	71
Limestone	103
Shale	123
Limestone	129
Shale	143
Limestone	190
Shale	195
Limestone	205
Shale	215
Lime	238
Shale	246
Lime	294
Shale	445
Limestone	457
Shale	505
Limestone	578
Shale	600
Limestone	622
Shale	628
Limestone	633
Shale	785
Sand show of oil	791
Shale	845
Gas Sand	860
Bottom	860

Well completed Feb. 18, 1903.
Well measured at 787 ft.
Packer placed 14 ft. from bottom

2 1/2 tenths mercury pressure on
5" casing = 4 1/2 million cu. ft.
per 24 hours. Initial flow.

Drip put in and operated. Well
showed a Rock Pressure of 275 lbs.
showed 2 pressure over 2" opening
or a volume of 1,140,500 cu. ft.
showed some water.
Included in sale of lease in June 1904