

1-27-25E

KELLY-CARTER COAL CO.

-Goble No. 1.

SEC. 1 T. 27 R. 25 E.
NE c SW

Total Depth. 1010
Comm. 9-4-37 Comp. 9-19-37
Shot or Treated.
Contractor. Phil Culbertson
Issued. 2-28-42

County Bourbon.



CASING.

8 1/4" 22' 6 1/4" 377'

Elevation.

Production. DRY.

Figures Indicate Bottom of Formations.

surface and clay	8	brown lime and white flint	550
coal	9-4	grey lime and white flint	570
fire clay and shalo	12	grey and brown lime wh and blue	
lime grey and calcite	15	flint	615
shale	20	brown lime and white flint	648
lime grey and calcite	24	green shale and lime shells and	
shale	30	white flint	650
shale blk some gas	35	sand grey shalo, white flint and	
shale grey	40	water	680
lime grey and calcite	43	grey shale sand and wh flint	695
shale grey and lime shells	90	lime brown white flint and mundie	705
shale grey	92	lime grey, selvage and wh flint	725
lime grey	93	brown and grey lime wh flint	740
shale blk	110	lime grey and grey flint	749
shale grey	155	shale blk and mundie	757
coal and grey shalo	160	lime grey flint grey, white sand and	
grand sand and trace of oil	167	mundie	760
shale grey	180	lime grey, white and blue flint, solvage	
lime grey	182	green shale seams and mundie	774
shale grey	205	white and blue flint, grey and brown	
sand grey some gas and water	253	lime and mundie	781
shale grey	260		
shale blk	268	grey blue and brown flint and	
shale grey and lime shells	290	mundie	805
grey sand and mundie	300	white and blue flint Mundie	810
grey lime, grey flint, mundie sand		grey blue and wh flint grey lime and	
shale and coal	305	solvage	840
grey blue, white flint and grey		broon lime blue and white flint	
lime, mundie	320	mundie	850
sand and white flint	325	flint blue and wh brown lime mundie	
blue and white flint grey lime	375	calcite	860
lime grey, some blue and grey flint	380	sand blue and white flint brown lime	
lime grey	390	solvage	870
lime grey, grey and blue flint	400	lime brown and white flint	875
grey and blue flint, some grey lime	410	grey blue and white flint, brown lime	
blue grey, and white flint and		and mundie	920
grey lime	415	grey blue and white flint, brown	
flint white and blue brown lime	420	lime and solvage	930
flint white and brown lime	475	brown lime white and blue flint	
white and light blue flint and		mundie	940
brown lime	480	brown lime wh flint and mundie some	
lime brown and seven wh flint	505	water	950
white flint brown and grey lime	515	brown lime grey lime mundie	960
brown and grey lime mud soams and		grey and brown lime wh flint and	
white flint	520	solvage	970
sdv br wh lime and wh flint	535	sand white and some lime	1010
		Total Depth	

Set 4" Pennon Pump at 220 feet, producing
approximately 85 gallons of water per
minute
Drawdown not available
Water fairly strong with
sulphur.