

25-27-3E

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- E. H. ADAIR OIL COMPANY
Farm- Lygrisse No. 1


SEC. 25 T. 27 R. 3E
NE NE NW

Total Depth. 3001'
Comm. 1-9-56
Shot or Treated.
Contractor. Adair
Issued. 11-3-56

Comp. 1-19-56

County Butler

KANSAS



Elevation. 1324.1 KB

Production. 144 BOPD

CASING:

8 5/8" @165' w/190 sx
5 1/2" @2989' w/50 sx

Figures indicate Bottom of Formations.

lime	355
lime & shale	1800
sand	1830
shale	1927
lime	1948
Oolitic lime	1954
lime	1980
lime & shale	2024
lime	2028
shale	2088
lime	2098
shale & lime	2116
shale	2274
lime	2280
Black shale	2281
shale	2335
lime	2406
shale	2414
lime	2417
shale	2421
shale & lime	2430
shale	2435
lime	2442
shale	2446
shale & lime	2469
shale	2500
lime & shale	2522
shale	2534
shale & lime	2552
lime	2562
shale & lime	2592
lime	2602
lime & shale	2625
Black shale	2627
lime & shale	2648
Black shale	2651
lime & shale	2670
shale	2689
lime & shale	2704
shale	2712
lime	2721
shale	2725
black shale	2726
lime & shale	2735
black shale	2737
lime & shale	2756
Chert	2760
lime	2743
shale	2746
lime	2761
shale	2765
lime	2778
shale & lime	2883
lime	2915
shale	2949
shale & siltstone	2958
shale	2989
sand	2993 RTD
sand	3001

Total Depth

TOPS:

Lansing	1927
Kansas City	2274
Mississippi	2756
Kinderhook	2915
Simpson	2989

DRILL STEM TESTS:

DST #1, 1948-55. op. 1 hr. shut
in 20". Weak blow thr. out. Rec.
18' drilling-mud. BHP 720#.

DST #2, 2987-93. op. 35". Shut in
20". Weak blow for 18". Rec 5' mud.
BHP 710#.