

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY.
 Union National Bank Bldg, Wichita, Kansas

H. & M. DRILLING CO.
 Suits No. 1.

SEC. 10 T. 27 R. 4E.
 CWL SW NW

Total Depth. 2014
 Comm. 12-6-34 Comp. 1-16-35
 Shot or Treated. 1000 gal acid.
 Contractor.
 Issued. 6-29-35

County. Butler.



CASING.
 10" 774' 6" 1989'
 8" 1420'

Elevation.

Production. 70 B.O.
 200 BW.

Figures Indicate Bottom of Formations

lime light	77	slate dark	1375
shale dark	90	lime light	1435
red rock	95	slate blue	1440
lime white	120	lime light	1470
slate white	160	slate dark	1495
lime grey	173	lime white	1515
slate dark	210	shale light	1595
red rock	220	lime white	1610
lime light	230	slate dark	1645
slate dark	250	lime white	1650
lime broken	475	slate dark	1675
shale dark	655	lime light	1850
slate light	680	shale dark	1989
lime light	685	Top of Kansas City lime	1989
shale dark	690	lime dark	1995
sand light	705	lime brown	2008
slate dark	765	lime grey	2014
lime grey	780	Total Depth.	
slate dark	790	<u>WATER RECORD.</u>	
lime grey	820	1/4" BW at	70
shale light	830	1/2" BW at	300
lime grey	850	2" BW at	660
slate light	882	6" BW at	700
lime light	900	1" BW at	920
slate light	915	1" BW at	1200
lime white	925	8" BW at	1720
slate light	950	HF.	1800
lime light	960	<u>GAS SHOWINGS</u>	
slate dark	965	Gas at 1200	
lime light	1005	Gas at 1400	
slate dark	1090	Gas at 1610	
lime white	1110	Oil and gas 1695	
slate dark	1135	Strong flow of gas from 2000-2005. 1st	
lime dark	1160	oil at 2008 to 2014 oil filled	
slate light	1175	up 800 feet in 2 hours. Well made 35 bbls	
lime light	1260	Hot and no water after treating with 1000	
slate dark	1270	gal it made 70 bbls oil and 200 bbls wtr	
lime white	1360		