

F. W. MORGAN
GEOLOGIST

P.O. BOX 18602
WICHITA, KANSAS 67218

Jan. 28, 1981

WICHITA OFFICE 685-6361
COYVILLE OFFICE 692-5473

Mr. Jimmy Razook
R. F. D. # 3
Rose Hill, Kansas, 67133

Re: Your No. 3 Born-Dondlinger
Sec. 28-27S-4E
Butler County, Kansas

Dear Sir:

Enclosed is my geological log on this well. The well ran about 15 feet lower than the No. 1 well to the south. Datum on Kansas City and Arbuckle formations is plotted on the log.

Shows of oil logged were as follows:


Arbuckle - 2491' to 2495' - This is the productive zone of No. 1. It did not drill as well as expected but shows of oil were found.
2460' - 2464' - This is the zone producing in Camio's well to the north. It should also be considered prospective in this well.
2443' - 2453' - This zone has not been found in your other wells with as good a drilling break or as good a show of oil. It should be considered prospective, especially the top 2 or 3 feet.

Kansas City - 2001' to 2006' - This is the zone found in Camio's well. It is better developed here than in your other two wells and should be considered prospective.

This well was taken to 2890' for possible disposal purposed and casing was cemented for testing zones in the Arbuckle and Kansas City.

Sincerely,


F. W. Morgan



**APPLICATION FOR DISPOSAL OF SALT WATER INTO
SALT WATER FORMATIONS**
(File 2 Copies)

TO
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
245 N. Water
Wichita, Kansas 67202

Field Name Augusta North
Lease Operator Jimmy Razook
Lease Name Born-Dondlinger
Legal Description of Lease W/2 of SW/4

Sec. 28 Twp. 27 Rge. 4 (E) (W)
County Butler

Application for SALT WATER DISPOSAL ORDER under Rules 82-2-400 to 405, of the Commission's General Rules and Regulations is herein submitted:

- A. Production map as required by Rule 82-2-400 and 403, (Map must show names of landowners and lessees and all wells on leases within one-half mile radius of the disposal well location and all leases and wells that may be connected to the disposal system.)
- B. Salt water is desired to be introduced into Arbuckle formation (s), which contain water as defined in Rule 82-2-400 "B", with (open hole) (perforations) from a depth of 2608 feet to a bottom depth of 2890 feet.
- C. Disposal is desired to be made into well No. 3 located 200 feet from the east line and 990 feet from the north line of the W/2 SW/4 of Sec. 28 Twp. 27 Rge. 4 (E) (W), Butler County, Kansas.
- D. Elevations of the producing formations in wells are:
(a) Shown on the production map; (X)
(b) Shown by tabulated statement attached hereto;
(c) Shown by well log information and surface elevations;
(d) Not required because water is being introduced into a salt water formation not known to be productive or expected to produce in this field.
- E. Disposal well log as required under Rule 82-2-403 "B" is:
(a) attached hereto; (X)
(b) to be filed on completion of the authorized disposal well.

- F. Casing information as required under Rule 82-2-401 is as follows: (Description of ALL casings in this well must be shown and verified by Driller's Log.)

SIZE	TOTAL LENGTH	SEAT DEPTH	CONDITION	CEMENTED OR MUDDERED	ESTIMATED FT. ENCASED IN CEMENT	NUMBER OF SACKS CEMENT USED
8 5/8	205'	205'	good	cemented	205'	130
5 1 1/2	2608'	2608'	new	cemented	600'	150

- G. Salt water, desired to be introduced, will be produced from the following described well (s) and lease (s):

LEASE OPERATOR	NAME OF LEASE	DESCRIPTION OF LEASE	WELL NUMBERS
Jimmy Razook	Born-Dondlinger	W/2 SW/4 Sec. 28-27S-4E	1, 2, and 4
Camio Oil Co.	McClure	SW/4 of NW/4 Sec. 28-27S-4E	1

and from any well or wells that may be drilled on the above described lease (s); estimated at 500 barrels per day minimum to 1,000 barrels per day maximum; to be introduced at:

- (a) gravity pressure at the well head; (X)
(b) or if necessary, with 50 pounds minimum pressure to 200 pounds maximum pressure at the well head.



H. A copy of this application with map attached, has been mailed or personally delivered to all operators of producing or drilling wells within one-half mile radius from the proposed disposal well location.

OFFSET OPERATOR'S CORRECT NAMEMAILING ADDRESS

Camio Oil Co.

2525 N. New York Bldg. 2 - Office 102
Wichita, Kansas, 67219E. B. McAllister
Samson Resource CompanyR. F. D. # 1 Leon, Kansas, 67074
2700 1st. Place

Hawkins Oil & Gas, Inc.

Tulsa, OK., 74103
Suite 701, 320 S. Boston Bldg.

Aspen Oil, Inc.

Tulsa, OK., 74103
7701 E. Kellogg, Suite 575
Wichita, Kansas, 67207

I. Regulations on HEARINGS UPON OBJECTIONS OR COMPLAINTS, are made a part of this application and are listed at the bottom of this page.

J. The Order requested by this application will not become fully effective until the following has been received by the Conservation Division:

- (a) a complete formation log of the disposal well
- (b) complete casing and cementing information
- (c) notification of the date water was first injected.

K. Supplemental information:

2 3/8" Fiberglass tubing at 950'

I hereby certify that the statements herein are true and correct to the best of my knowledge and belief.

Applicant or Duly Authorized Agent:

Jimmy Razook

Subscribed and sworn to before me this _____ day of _____, 1981

Notary Public.

My Commission expires _____

Address all correspondence to: _____ Jimmy Razook

Address: _____ R. F. D. # 4, Augusta, Kansas

REGULATIONS ON HEARINGS UPON OBJECTIONS OR COMPLAINTS

Rule 82-2-403

"F" Objections or complaints, stating the reasons why the proposed plan as contained in the application may cause damage to oil, gas or fresh water resources, must be filed within ten days after the application is filed.

"G" In the event any such objection or complaint is filed or the Commission on its own motion deems that there should be a hearing on the application, a hearing shall be had after reasonable notice of the time, place and subject matter of such hearing has been given to the parties in interest.

"H" Orders approving the disposal plan will not be made within ten days of the filing of the application unless the written consent of all persons entitled to notice is filed with the Commission within such time.

NOTE: Any objections to or complaints of this application are to be filed with THE STATE CORPORATION COMMISSION,
State Office Bldg., Topeka, Kansas 66612