

F.W. MORGAN

GEOLOGIST

305 S. WASHINGTON
EL DORADO, KANSAS 67042

Ja. 18, 1991

(316) 321-1463

Razook Oil Co.
Route 4, Box 102
Augusta, Kansas, 67010

Re: No. 6-A Anderson
Sec. 9-27S-4E
Augusta, Kansas

Gentlemen:

Enclosed is my geological log on this well. The Well ran 6' to 10' low on subsurface markers compared to high wells on the lease down to the Arbuckle. Here it was 2' feet higher than No. 1-A, the highest well on the lease. Below are listed prospective producing zones as logged:

Lansing - 1687-1698 - Limestone, tan, oolitic, porous, good show of free oil, odor, staining.

Kansas City - 1982-1985 - Limestone, brown, fine vugular and oolitic porosity, good show of free oil, odor, staining.

- 2002-2018 - Limestone, white, dense, porous, show of free oil, odor, staining. Bottom 3 to 4 feet does not carry staining.

Arbuckle - 2380-2386 - Dolomite, tan, dense, slight vugular porosity, free oil (slight), odor, staining.

2382-2385 - Dolomite, very fine grained, some vugular porosity, free oil, odor, stain.
(covered by drill stem test)

Zone 2392-2398 also covered by drill stem test is not recommended.

Zone 2456-242464 had no show of oil but some intercrystalline porosity and should be considered for water disposal.

All depths given are subject to correlation with GRN log.

Sincerely,

F. W. Morgan

