

MORGAN GEOLOGICAL SERVICES, INC.

P.O. BOX 18602
WICHITA, KANSAS 67218

May 11, 1981

WICHITA OFFICE 685-6361
COYVILLE OFFICE 692-5473

Razook Oil Co.
R. F. D. # 4
Augusta, Kansas, 67010

Re: No. 2 Dehler
Sec. 34-27S-5E
Butler County, Kansas

Gentlemen:

Enclosed is my geological log on which I have plotted all formation tops, sand zones, shows of oil, etc. This well appeared to run about flat with the No. 3-A Fleming. However, the sand was thicker and better developed (thicker) and has just as good an oil show. My recommendations for perforating are as follows:

2737 - 48 - Fine sand with no show of oil, fluorescence or odor.

2748 - 72 - Medium Grain sand with porosity, free oil, fluorescence and odor.

I recommend that you begin perforating no higher than 2748' and go as deep as you need to. Although the fine sand from 2737 to 2748 will probably appear on the GRN log it does not carry oil and should not be perforated. Casing was run to 2835' to test the sand.

Sincerely,



F. W. Morgan

