

Buffalo Brick Co. Well No. 8 on the Henry Ferris, Famr.  
Well drilled in Monday noon May 3th, 1904.

20	Surface, fresh water 15 ft.	20
50	shale	70
55	lime, salt water 85	125
55	shale	180
45	lime	225
70	shale, coal 240	295
90	lime	385
5	B. slate & water	390
85	lime	425
5	shale	430
60	lime	490
110	shale	600
10	lime	610
80	shale, little gas 690 ft.	690
35	lime	725
30	shale	755
10	lime.	765
5	B. slate, gas & water	770
10	lime	780
148	shale, gas 800	928
7	oil sand	935
60	shale	995
20	gas sand	1015
5	slate	1020
10	sand	1030
20	shale	1050
10	salt sand	1060

8 1/2" casing. 43 ft.  
6 1/2" casing. 477 ft.  
4-7/8" casing. 915 ft.

Dry Hole