

10" 1521 FARM J.T. Barnhill NO. 3 COUNTY Butler.
 20" 8 1-4 2238 COMPANY Phillips Petroleum Company.
 15 1-2 6 5-8 2622 CONTRACTOR
 12 1-2 869 5 3-16 COMMENCED 1-5-27 COMPLETED 2-9-27
 TOTAL DEPTH SHOT 180 QUARTS BETWEEN 2621-2677
 CORRESPONDENCE REGARDING THIS WELL SHOULD BE REFERRED TO Phillips Petroleum
 Company. Bartlesville, Okla.
 FIGURES INDICATE BOTTOM OF FORMATIONS. ELEVATION
 REMARKS 4-19-27 INITIAL PRODUCTION 352bbbls.



Top of sand 2621. Top of first oil 2621-2626. Bottom oil sand 2677. Total Depth 2677. Present total 2677. Grey.

Formation	Depth	Formation	Depth.
celler	6	lime white hard	1080
clay yellow soft	10	shale white soft	1090
lime white hard	30	lime white hard	1095
shale blue soft	40	shale white soft	1110
red rock red soft	50	lime white hard	1135
shale blue soft	80	LBW 1130	
lime white hard	100	slate blue soft	1145
shale blue soft	120	lime white hard	1170
lime white hard	130	shale white soft	1205
shale blue soft	165	lime white hard	1215
lime white hard LBW 175	185	shale white soft	1250
red rock red soft	190	lime white hard	1260
shale blue soft	200	slate white soft	1285
lime white hard	215	lime white hard	1295
shale blue soft	330	slate blue soft	1300
shale white soft	360	lime white hard	1335
lime white hard	370	shale blue soft	1375
slate blue soft	410	lime white hard	1390
lime white hard	420	shale blue soft	1410
red rock red soft	430	6BW 1425	
slate blue soft	455	sdv shale grey soft	1425
lime white hard	470	HFW 1435.	
slate white soft	500	sand grey soft	1515 SL.
shale blue soft	560	shale blue soft	1560
lime white hard	570	lime white hard	1580
slate blue soft	600	shale white soft	1675
lime white hard	610	lime wh hard	1820
shale blue soft	665	2BW 1750	
lime white hard	685	shale blue soft	1975
shale blue soft	710	show oil. 2005	
lime white hard	740	lime white hard	2100
shale blue soft	745	lime wh hard	2135
lime white hard	755	HFW 2150	
shale blue soft	790	lime sdv white hard	2200
lime white hard	795	shale blue soft	2234
shale blue soft	865	8 1/4 2234	
12 1/2 869 SLM		shale dark soft	2310
lime white hard	880	lime wh hard	2315
shale blue soft	885	shale dark soft	2375
lime white hard	890	lime wh hard	2395
shale dark soft	895	shale dark soft	2405
shale blue soft	905	lime white hard	2420
lime white hard	935	shale dark soft	2530
shale blue soft	975	shale light soft	2600
lime white hard	1005	6-5/8 2613 SL.	
shale blue soft	1015	shale sdv grey soft	2621
lime white hard	1045	oil sand	2677
shale blue soft	1065	T.D.	2677