


PHILLIPS PETRO.CO.
 Keighley No. 26.

SEC.23 T.27 R.7 E
 CSW NW
 660 WL 660'SL NW $\frac{1}{4}$

County. Butler

Total Depth. 3164'
 Comm. 7-10-41 Comp. 8-20-41
 Shot or Treated.
 Contractor.
 Issued. 11-22-41



CASING:
 8" 132'
 5" 3153'

Elevation.

Production. Pot. 293 B.
 5% B.S.

Figures Indicate Bottom of Formations.

lime	26
sand	35
lime & shale	143
lime, shale, sand	363
lime & shale	1363
shale	1577
lime & shale	1764
lime	1785
shale & lime	1870
lime	1981
lime & shale	2073
lime, spotted sat.	2082
lime, showing slight stain & odor of oil	2089
lime	2120
lime saturated	2128
lime	2311
lime & shale	2690
sand w/no sat.	2698
shale sdy	2706
sand	2708
shale sdy	2712
sand, well saturated	2738
sand saturated	2764
lime	2785
lime, well saturated	2786
lime	2796
lime brown showing oil stain	2797
lime shaly sft	2798
lime cherty showing some saturation	2799
lime brown	2800
lime	2803
lime cherty	2815
lime, chert, shale	2843
lime & shale	2891
lime	2932
chert	2936
lime & chert	2955
lime cherty	2985
lime & chert	3023
lime	3056
lime, strks shale	3080
lime	3135
shale blk	3153
lime dolomitic	3159
lime	3164
Total Depth.	

Pot. 293 Bbls, 5% B.S.
 after 500 Gals. Acid