

10" 1620 FARM W.J. Trousdale NO. 5 COUNTY Butler
 20" 8 1-4 2201 COMPANY Phillips Petroleum Co.
 15 1-2 6 5-8 2708 CONTRACTOR J.D. Mandeville.
 12 1-1005 5 3-16 COMMENCED Feb 21, 1926 COMPLETED March 22, 1926

TOTAL DEPTH 2755

SHOT

QUARTS BETWEEN

CORRESPONDENCE REGARDING THIS WELL SHOULD BE REFERRED TO Phillips Petroleum
 Company, Bartlesville, Okla.

ELEVATION 1406-6G

INITIAL PRODUCTION 200 bbls.

FIGURES INDICATE BOTTOM OF FORMATIONS.

REMARKS

Formation	Depth	Formation	Depth.
soil and clay soft	10	lime white hard	1247
lime white hard	25	shale white soft	1257
shale gray soft	45	lime white hard	1267
lime white hard	65	shale white soft	1283
rock red soft	80	lime white hard	1315
shale blue soft	100	shale blue soft	1355
lime white hard	110	lime white hard	1400
red rock soft	150	shale blue soft	1405
lime white hard	180	lime white hard	1440
shale blue soft	260	rock red soft	1450
lime white hard	290	shale white soft	1570
shale white hard	330	sand white hard HFW	1590
lime white hard	360	lime white hard	1635
shale blue soft	375	set 10" 1620 SLM	
lime white ard	395	shale white soft	1675
shale dark soft	500	lime white hard	1695
lime white hard	520	shale white soft	1756
shale blue soft	570	lime big lime white hard	1912
lime white hard 3BW	600	2BW at 1840	
shale blue soft	640	shale blue soft	1982
lime white hard	670	shale white soft HFW	2080
shale blue soft	710	HFW 2175	
lime white hard 5BW	725	lime Oswego white hard	2240
shale blue soft	775	set 8 1/4 2200 SLM	
lime white hard	825	shale white soft	2475
shale blue soft	955	lime white hard	2535
lime white hard	980	shale white soft	2702
shale dark soft	1000	set 6-5/8 csg SLM	2702
lime white hard set 12 1/2	1007	sand brown soft	2710
casing at 1007 S.L.M.		1st oil 2710	
shale white soft	1084	sand dark soft	2752
lime white hard	1092	T.D.	2755
shale white soft	1127		
lime white hard	1157		
shale white soft	1177		
lime white hard	1197		
shale white soft	1227		