


10' 1609 FARM W. J. Trousdale NO. 8 COUNTY Butler
 20" 8 1-4 2202 COMPANY Phillips Petroleum Company.
 15 1-2 6 5-8 2693 CONTRACTOR
 12 1-2 10 1 5 3-16 COMMENCED 4/21/26 COMPLETED 5/23/26



TOTAL DEPTH SHOT 100 QUARTS BETWEEN

CORRESPONDENCE REGARDING THIS WELL SHOULD BE REFERRED TO Phillips Petroleum Company, Bartlesville, Oklahoma. ELEVATION 1507.5 G.
 FIGURES INDICATE BOTTOM OF FORMATIONS. INITIAL PRODUCTION 125 bbls.

REMARKS

Formation	Depth	Formation	Depth
cellar	5	shale blue soft	1550
clay yellow	10	sand gray soft (10 BW 1590')	1615
lime white	25	shale blue (10" at 1617')	1617
shale blue	50	shale blue soft	1680
lime white	60	lime white hard	1700
red rock	80	shale blue	1775
lime white	120	lime white hard	1780
shale blue	160	shale blue soft	1785
lime white	200	lime white hard (2 BW at 1835)	1840
shale dark	210	lime white hard	1890
lime white	260	shale blue soft	1895
shale blue	300	lime white hrd (1 BW at 1930')	1935
broken lime	350	shale blue soft	2095
shale blue	400	lime white hrd (6 BW at 2145')	2160
lime white	425	lime white hrd (HFW at 2165)	2180
shale blue	440	lime white hrd	2200
lime white	460	shale blue soft	2205
lime white	430	lime white hrd (8 1/4" at 2210')	2215
shale blue	600	lime white hrd	2250
sand, gray (10 B.W. per hr. 605')	620	sand gray soft (1/2 BW at 2265')	2280
shale blue	630	shale blue soft	2375
lime white	650	shale white soft	2400
shale blue	775	lime white hrd	2415
lime white	785	shale blue	2425
shale blue	835	lime white	2435
lime white (5 BW per hr 845')	850	shale blue soft	2480
shale blue	900	lime white	2490
shale & shells	970	shale blue	2500
shale blue	980	lime white	2510
lime white	985	shale dark	2515
shale blue	1000	lime white hrd	2550
lime white	1005	shale blue soft	2600
shale blue (12 1/2" at 1020')	1020	shale blue	2635
shale blue	1070	lime white hard	2645
shale & shells	1135	shale blue soft	2665
lime white	1150	sandy shale	2699
shale blue	1175	(6 5/8" at 2699')	
lime white	1185	sandy shale	2725
shale blue soft	1235	sandy shale	2747
lime, white, hard	1245	sand first oil	2757
shale blue, soft (cave 1280')	1265	slate break	2759
lime, white, hrd (to 1310')	1280	oil sand	2777
shale, blue soft	1310	Total Depth	2777
lime white hard	1315		
lime white hard	1335		
shale blue soft	1400		
lime white hard	1440		
lime white hard	1450		
shale pink	1485		
lime white	1480		
shale blue soft	1500		