

25-27-8E

BEAUMONT OIL CO.
Lewis "A" No. 7.

SEC. 25 T. 27 R. 8E
NEc SW

DEEPENING RECORD.

Total Depth. . 2756 P.B. 2757½
Comm. 3-21-41 Comp. 5-24-41
Shot or Treated.
Contractor. None
Issued. 4-11-42

County. Greenwood



CASING:

15" 21' Cem. 7" 2428' Not Cem.
12½" 749' P 5" 2738' cemented.
10" 1124' P
8" 1350' UR 1498' 11" P

Elevation.

Production. 15 Bbls.
Est. Natural

Figures Indicate Bottom of Formations.

lime	3	lime hrd	990
lime shells	20	shale	995
lime	40	red rock	1000
shale	90	shale	1025
lime	95	lime	1035
shale	115	shale	1050
lime	120	shale & shells	1055
red rock	125	lime	1060
shale	130	shale	1090
lime	135	lime	1098
red rock	145	shale	1108
shale	165	gas sand	1121
lime	170	shy shale	1124
shale	245	shale	1155
lime	250	lime	1160
shale	280	shale	1245
lime	285	lime	1255
shale	300	shale	1280
lime	305	lime	1290
shale	340	shy lime	1310
lime	360	wtr sand	1340
shale	375	lime	1490
lime	410	shale	1635
shale	415	lime	1645
lime	420	shale	1655
shale	460	lime K.C.	1665
lime	465	shale	1670
shale	485	lime	1695
lime	500	gas sand	1705
shale	505	467,000 G. 1695-1705	1743
lime	510	lime	1743
shale	535	oil show 1748	1758
lime	585	lime	1765
shale	625	shale	1813
lime	630	lime	1843
shale	635	Peru sand	1843
lime	660	sh oil 1824 SLM	1850
shale	665	lime	1850
lime	693	shy shale	1905
shale	696	shale	1950
lime hd	705	lime	1955
shale	720	shale	1965
lime	725	lime	1970
shale	730	shale	1995
lime	735	lime	2000
red rock	749	shale	2070
lime	752	lime	2095
shale	760	shale	2110
lime	765	lime	2120
shells & shale	790	shale	2125
shale	798	lime	2130
lime	815	shale	2300
shale	860	red rock	2305
lime	870	shale	2383
shale	897	lime	2385
lime shell	900	shale blk	2402
gas sand	905	Burgoss sand	2426
shale	945	Top Miss 2426 SLM	2454
lime	935	lime	2473
		lime blk	2473
		lime	2500

DEEPENING RECORD.

lime dk 2522
lime gy 2528
lime sdy 2540
line 2551 SLM
Total Depth.
Plugged back to 2534
Gas Shows:
Helium gas 900-05
150,000 cu ft 1108 to 1121
467,000 cu ft 1695 to 1705
Oil shows:
oil sh(lgt) 1743-48
free oil 1824-30 SLM
2 gals. oil per hr 1830-34
Hole filled 600' 8 hrs 2528-40
Est. Natural 15 B.
Wtr Record:
2½ BWPH at 965 (11" x 17' bailer)
1 BWPH at 1095 (11" x 17' bailer)
HFV 1315-40
5 BWPH 1385-99 (7" x 32' bailer)
Tops:
KC lime 1655
Peru sand 1824 SLM
Mississippi lime 2426 SLM
5-15-41 500 Gals.
5-25-41 1000 Gals.
6-30-41 1500 Gals.

Comm. 9-18-41
Comp. 10-7-41
Prod. Est. 45 B.
5" 2738' com

grey lime 2695
shale blk 2739
Wilcox sand oil 2739½
(33 Gr Corrected)
400' fillup
Wilcox sd 2742
shale green 2745
sand hd 2753
Arbuckle 2758 SLM
Total Depth. P.B. 2757½
1st oil 2755
1st free oil 2756-57
Top Arbuckle 2753
200' fillup per hr.
Total fillup 2000' (27.5 Gr. corrected)