

COPY


INLAND OIL CO.  
J. P. Lucas No. 3.

SEC. 6 T. 27 R. 8 E

Center Lot 25 (600'W, 600'S NE  
Lot 25)

Total Depth. 2725'  
Comm. 2-9-22 Comp. 4-5-22  
Shot or Treated. 20 Qts. 2710-20 4-6-22  
Contractor.  
Issued.

County. Butler  
KANSAS



CASING:  
12 1/2" ? 314'10"  
12 1/2" ? 848'8"  
10" 1242'11"

8 1/4" 2027'11"  
6 5/8" 2425'  
5 3/16" 2694'

Elevation.

Production. Dry

Figures Indicate Bottom of Formations.

|                        |      |                        |      |
|------------------------|------|------------------------|------|
| soil blk sft           | 5    | shale sft              | 1685 |
| mud gy sft             | 35   | lime shell             | 1690 |
| lime hd                | 50   | shale sft (2BW 1858)   | 1700 |
| red rock sft           | 55   | lime wh hd             | 1860 |
| sdv lime sft 2BW 55    | 65   | shale dk sft           | 2005 |
| mud sft                | 125  | lime wh hd             | 2165 |
| lime hd                | 155  | 8 1/4" csg at 2027'11" |      |
| shale sft              | 160  | shale blue sft         | 2175 |
| lime hd                | 170  | 1BW 2115; 2BW 2180     |      |
| shale sft              | 190  | sand dk sft            | 2200 |
| sand sft HFW 190       | 205  | shale dk sft           | 2280 |
| red rock sft           | 210  | lime wh hd             | 2300 |
| shale sft              | 220  | shale lgt sft          | 2325 |
| sdv lime sft           | 270  | lime dk hd             | 2337 |
| shale sft              | 285  | shale wh sft           | 2390 |
| lime hd                | 300  | lime wh hd             | 2408 |
| shale sft              | 305  | slate blk sft          | 2424 |
| lime hd                | 320  | lime shell sft         | 2425 |
| 12 1/2" csg at 314'10" |      | 6 5/8" csg at 2425     |      |
| shale sft              | 330  | lime dk hd             | 2440 |
| lime hd                | 350  | shale wh sft           | 2540 |
| shale sft              | 440  | shale gritty sft       | 2570 |
| lime hd                | 470  | 1 BW 2550              |      |
| slate sft              | 510  | slate wh sft           | 2600 |
| lime hd                | 560  | shale sand dk gy       |      |
| slate sft              | 600  | sft                    | 2670 |
| lime hd                | 630  | shale dk sft           | 2695 |
| slate sft              | 660  | 5 3/16" csg at 2694    |      |
| lime hd                | 700  | coal dk sft            | 2697 |
| slate sft              | 720  | shale dk sft.          | 2711 |
| lime hd                | 760  | cave at 2706           |      |
| sand sft HFW 765       | 770  | sand brown sft         | 2721 |
| lime hd                | 780  | show of oil washed     |      |
| slate wh sft           | 895  | out good               |      |
| 12 1/2" csg at 848'8"  |      | gas smell              |      |
| lime wh hd             | 910  | 2 BW 2724-25           |      |
| slate dk sft           | 1010 | sdv lime hd            | 2725 |
| lime wh hd             | 1095 | Total Depth.           |      |
| slate dk sft           | 1110 |                        |      |
| lime wh hd             | 1170 |                        |      |
| slate sft              | 1180 |                        |      |
| lime hd                | 1195 |                        |      |
| slate sft              | 1200 |                        |      |
| lime wh hd             | 1225 |                        |      |
| cave 1225-50           |      |                        |      |
| slate sft              | 1250 |                        |      |
| 10" csg 1242'11"       |      |                        |      |
| lime hd                | 1263 |                        |      |
| shale wh sft           | 1285 |                        |      |
| lime hd                | 1300 |                        |      |
| shale sft              | 1335 |                        |      |
| lime wh hd             | 1425 |                        |      |
| slate wh sft           | 1435 |                        |      |
| shale sft              | 1495 |                        |      |
| lime wh hd             | 1505 |                        |      |
| sand gy sft            | 1545 |                        |      |
| 4 BW 1520              |      |                        |      |
| slate wh sft           | 1570 |                        |      |
| shale sft              | 1605 |                        |      |
| lime wh hd             | 1640 |                        |      |