

Location NW $\frac{1}{4}$  Sec 8 T. 27 R 17  
Clara U. Peterson No. 3 Wilson  
Co Ridge Gas Co Date 5/16-29  
T. D. 1010'

Hole filled with mud from 10108 to 996', 6 $\frac{1}{4}$ " wood plug set at  
993' and hole filled with mud from there to 515', 8" wood plug set at 434'  
and hole filled with mud from there to within 8' or top where hole was  
plugged with an 8' wood plug.

Formation	Depth
Clay	15'
Shale	40
lime	70
shale	80
lime	93
shale	95
lime	148
shale	240
lime	315
shale	320
lime	362
shale dark	365
lime	395
shale	397
lime	433
shale	515
lime	535
shale	543
lime	555
shale	642
lime	669
shale	697
lime	712
shale	717
lime	772
shale	835
shale black	895
shale do	949
shale do white	1010