

16-28-1E


WELL LOG BUREAU--KANSAS GEOLOGICAL SOCIETY
412 Union National Bk. Bldg., Wichita, Kansas

Company - E. B. SHAWVER
Farm - Brookings "A" No. 3

SEC. 16 T. 28 R. 1E
SE NW SW
1050' fr WL, 900' fr NL of SW/4

Total Depth. 3095'
Comm. 6-10-49 Comp. 6-28-49
Shot or Treated. June 28, 1949 w/4000 gals. acid.
Contractor. E. B. Shawver
Issued. 7-23-49

County. Sedgwick
KANSAS



Elevation. 1272' *2nd*

Production. Est. 20 BOPD on pump

CASING:
8 5/8" 86' cem w/65 sx.
5 1/2" 3070' cem w/50 sx.

Figures indicate Bottom of Formations.

sand	15
sand, gravel	37
shale, shells	86
lime brkn	554
shale, shells	1703
lime	1760
shale, shells	1865
lime	2040
shale	2590
K. C. lime	2773
shale	3071
Correction to DFM	
3071 = 3069	
lime, chert	3091
chert white	3095
Total Depth	

Tops:

Kansas City Lime DFM 2588
Chat 3069

IP 200' of oil in hole in 24 hrs.
Well tested 20 BOPD on pump
after acid.