


WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY
508 E. Murdock Wichita, Kansas

Company - BLACK SUPPLY CO ETAL
Farm Lee No. 1

SEC. 16 T. 28 R. 1E
SE NW SW NW
850' fr SL 560' fr WL NW $\frac{1}{2}$

Total Depth 3099
Comm. 12-5-49 Comp. 12-18-49
Shot or Treated Acidized with 2000 gals
Contractor. Penguin Petroleum
Issued. 2-18-50

County. Sedgwick
KANSAS



CASING:
8 5/8" 100'
5 1/2" 3072'

Elevation. _____

Production. Init. Pot. DRY

Figures Indicate Bottom of Formations.

surface sand	50
shale and lime	330
shale and shells	465
lime	505
shale and shells	550
lime and shale	770
shale and lime	950
shale and shells	1415
shale & lime shells	1670
lime	1765
shale and shells	1795
bkn lime	1950
lime and shale	2080
lime bkn	2200
lime	2320
shale and lime	2395
shale and shells	2505
shale	2600
lime	2640
lime and shale	2670
lime	2824
shale and lime	2890
lime	2974
shale and shells	3060
shale	3070
lime R.T.D....	3072 R.T.D....
3072' equals 3074' S.L.M.	
R.U.S.T.	
Dolomite	3099
Total Depth	

TOPS:
Kans City limestone 2595
Miss. Dolomite 3072' corrected

2

Acidized with 2000 gals XX acid
Swabbed wtr and show of oil
Plugged back with plastic to 3091 $\frac{1}{2}$
Swabbed 1 brrl acid wtr per hr
Plugged back with plastic 3084'
 $\frac{1}{2}$ bailer acid an load wtr per hr and show oil
POP, could not pump, plugged and abandoned