


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY  
508 East Murdock, Wichita, Kansas

Company- BEARDMORE & SUTTON  
Farm- Tyson No. 3

SEC. 30 T. 28 R. 1E  
SW NW SE

Total Depth. 3191  
Comm. 12-4-54 Comp. 12-17-54  
Shot or Treated.  
Contractor. Beardmore Drlg.  
Issued. 2-26-55

County Sedgwick  
KANSAS



CASING:

8 5/8" 123' cem. w/100 sx  
8 5/8" recemented at 129' with 60 bx & 30 sx on top  
5 1/2" 3160' cem. w/50 sx

Elevation. 1264 DF

Production. 316 bbls. oil

Figures indicate Bottom of Formations.

|              |      |
|--------------|------|
| cellar       | 5    |
| sand         | 60   |
| shale        | 129  |
| shale & lime | 3191 |
| Total depth  |      |

|               |      |
|---------------|------|
| Tops:         |      |
| Mississippi   | 3146 |
| Dolomite      | 3163 |
| Limy Dolomite | 3163 |

DST #1 3161-3191-Gas in 45 minutes, shut in 20 minutes. flowed when releasing pressure after shut in; circulated oil out. sub was 120' off bottom, recovered fluid estimated as follows: 3070' oil, 120' oil cut mud, no water; IF 155', FF 800, BHP 1100, IH 1750, 3190, ran 5 1/2 csg. to 3160.