

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY.
412 Union National Bank Bldg, Wichita, Kansas.

STEINBUSHEL ET AL.
Martin No. 1.

SEC. 18 T. 28 R. 1E.
SEC NW

Total Depth. 3494
Comm. 8-22-37 Comp. 10-25-37
Shot or Treated.
Contractor. I. W. Murfin.
Issued. 11-6-37

County. Sedgwick.

CASING.

15 1/8" 73'8"
12 1/8" 1002' UR 1117'
10" 1946'
8 1/2" 2395' UR 2730'
6 5/8" 3489'

Elevation. 1275

Production. 52 B. 2nd hr.

Figures Indicate Bottom of Formations.

cellar	8	lime	760	shale	1360
sand	54	shale	770	lime	1365
shale	90	lime	785	shale	1380
lime	95	shale	790	lime	1385
shale	105	lime	830	shale	1395
lime	115	shale	835	lime	1400
shale	140	lime	845	shale	1410
lime	155	shale	850	lime	1425
shale	170	lime	860	shale lime sholls	1460
lime	175	shale	870	lime	1480
shale	180	lime	905	shale	1500
lime	190	shale	910	lime	1510
shale	195	lime	915	shale and lime	1525
lime	210	lime	930	lime	1560
shale	220	shale	940	shale	1570
lime	235	lime	945	lime	1575
shale	245	shale	950	shale	1600
lime	255	lime	955	lime	1620
shale	265	shale	960	shale	1625
lime	275	lime	975	lime	1685
shale	280	shale	985	shale	1725
lime	285	lime	1005	lime	1755
shale	300	shale	1025	shale	1760
lime	310	lime	1030	lime	1795
shale	360	shale	1050	shale	1810
lime	385	lime	1055	lime	1830
shale	390	shale	1070	shale	1835
lime	395	sand water	1085	lime	1865
red rock	400	shale	1117	shale	1870
shale	415	lime	1121	lime	1935
lime	455	shale	1125	1935 equals 1946	
shale	470	lime	1130	lime	2040
lime	565	shale	1155	shale	2045
lime broken	580	shale lime sholls	1190	lime	2050
lime	590	shale	1200	shale	2055
lime broken	605	lime	1205	lime	2090
lime	655	shale	1220	shale	2285
shale	660	lime	1225	lime	2290
red rock	665	shale	1255	sand	2300 HFW
lime	680	lime	1260	lime	2315
shale	690	shale and lime	1270	shale	2340
lime	695	shale	1280	lime	2355
shale	700	lime	1285	shale	2385
lime	725	shale	1295	lime	2410
shale	740	lime	1300	shale	2430
lime	750	shale	1320	lime	2435
shale	755	lime	1335	lime broken	2450
				shale	2612

OVER

18-28-1E.
 Martin No. 1.
 Steinbushel et al. Sedgwick Co.

lime	2620
shale	2622
lime	2725
shale blk	2730
lime	2795
shale	2850
lime and shale	2865
shale	2895
lime	2900
shale	2910
lime	2925
shale	2930
lime	2935
shale	2940
lime	2950
shale	2960
lime	2965
shale	2975
lime	2985
shale	3005
shale and lime	3015
lime	3020
shale shells	3030
lime	3035
shale	3040
lime	3045
shale	3050
rod rock	3053
shale	3080
shale lime shells	3090
chat	3105
lime	3355
shale green	3360
lime	3385
shale green	3395
shale	3400
lime	3420
shale	3460
lime	3465
shale	3475
shale blk	3490
sand Wilcox	3494

Total Depth.
 Hole filled up 600' in 30 Min
 Pumped 28 bbls 1st 30 Min.
 Pumped 48 bbls 1st hour
 Pumped 52 bbls 2nd hour

7 BW 915
 HFW 1070-85
 3 BWPFR 1530
 HFW 1925
 $1\frac{1}{2}$ BW 1965-75
 HFW 2290-95
 1 BW 2665
 HFW 2695-2700
 some water 3200

3090
 1275
 -1815

5122-
 5121
 0645