


KANSAS WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY.
Union National Bank Bldg, Wichita, Kansas.

THE DICKEY OIL COMPANY.
Riley No. 1.

SEC. 20 T. 28 R. 1E.
SE NE SW

Total Depth 3124,
Comm. 11-19-34 Comp. 12-14-34
Shot or Treated,
Contractor.
Issued. 2-2-35.

County. Sedgwick.



CASING.

10" 88' 65/8" 3090'

Elevation.

Production. Pot. 598 B.

Figures Indicate Bottom of Formations.

sand	50	shale	2589
shale gravel	70	K.C. lime	2637
broken lime	88	broken lime	2652
shale and shells	125	lime	2681
shale	155	shale	2703
broken lime	180	lime	2725
shale	205	shale	2730
lime	225	lime showing oil	2810
shale	245	broken lime	2850
lime	295	shale sticky lime shells	2950
broken lime	325	broken lime	3000
shale	405	shale	3035
lime	460	lime grey	3043
shale and shells	490	shale colored slightly	3063
lime	510	shale	3065
shale	540	lime	3070
lime	565	shale	3073
broken lime	860	variegated shale and red	
shale and shells	960	bed	3086
lime	990	cased to 3086	
shale and shells	1230	lime	3088
shale	1375	colored shale	3092
broken lime	1490	red rock	3095
shale	1624	peppery lime	3097
lime brown	1650	lime white	3099
water sand	1660	lime brown	3103
lime	1675	show of oil	3102
shale	1710	lime brown coarse	3120
lime	1740	600' oil at	3104
shale	1750	lime brown	3124
lime	1755	Total Depth.	
shale soft	1794		
lime	1850		
shale	1854		
lime	1895		
shale	1915		
lime	1925		
shale	1995		
lime	2005		
shale	2045		
broken lime	2085		
shale	2335		
water sand	2375		
broken lime	2450		