

UNION NATIONAL BANK BLDG WICHITA KANSAS.

Location Cen SE SW

Sec. 27 T. 28 R. 1E.

Casing Record

County- Sedgwick.


10" 1944
20" 73'7" 8 1/4" 2770
15 1/2" 203'6" 65/8" 3160'
12 1/2" 1250 53/16"

Farm- Russell No. 1
Company- Aladdin Petr. Corp.
Contr.- Rosenthal & Beardmore Drlg. Co.
Comm.- 10/3/1930. Comp.- 11/27/30.

Total Depth 3608'.

Shot Quarts Between

Correspondence Regarding This Well Should Be Referred to



Elevation

Figures Indicate Bottom of Formations.

Initial Production Dry.

Date Issued. 12/6/1930'.

Formation	Depth	Formation	Depth	Formation	Depth
sand	30	lime	1675	lime	3500
shale	60	shale	1720	lime shells &	
gravel	65	lime	1750	shale	3510
shale	105	shale white	1760	B. shale	3582
lime	150	lime shells	1770	sdv lime	3608
shale	165	shale	1800		
lime	190	lime	1810	Total Depth	3608
shale	205	shale	1830		
GYP	210	lime	1910		
shale	215	sdv lime	1915		
lime	260	lime	1920		
shale gray	275	sand	1935		
lime	285	lime	2040		
shale blue	290	shale drk	2065		
shale & lime	325	lime	2080		
shale & lime	450	shale	2100		
lime	540	lime	2150		
shale	565	sand & shale	2275		
red rock	570	shale	2285		
shale blue	575	lime	2290		
lime	630	W. sand	2315		
red rock	645	sand	2400		
lime	670	lime	2405		
shale	680	sft lime	2625		
lime	690	lime hrd	2635		
shale	710	lime	2685		
lime & shale	850	sand	2695		
shale	860	lime	2720		
lime	925	sand	2725		
shale	930	lime	2750		
lime	970	sand	2790		
shale	975	lime	2830		
lime	985	shale blue	2832		
shale	1020	lime	2850		
lime	1025	shale	2880		
shale	1075	lime	2910		
lime	1085	red rock	2915		
shale	1100	lime	2935		
lime	1105	shale	2950		
shale	1125	brkn lime	2960		
lime	1130	shale	2965		
shale	1155	lime	2995		
lime	1160	shale	3035		
shale	1175	lime	3050		
lime	1185	shale	3070		
shale	1240	lime	3093		
sand	1247	shale	3101		
lime	1255	lime shells	3145		
shale	1270	red rock	3155		
lime	1275	various color shale	3160		
shale	1295	lime	3163		
shale & lime	1360	V. C. shale	3200		
lime shells	1430	lime sharp	3206		
sdv lime	1455	V. C. shale	3225		
shale	1485	lime shells	3235		
lime	1500	lime	3290		
sdv lime	1535	shale	3295		
shale	1540	lime	3460		
lime	1575	shale	3470		
shale & shells	1620	lime	3475		
		shale	3478		

WATER RECORD

HFV	60
1 BW per hr	845
10 BW per hr	1245
1 BW per hr	1295
2 BW per hr	1430-55
2 BW per hr	1500-1520
3 BW per hr	1520-1535
HFV	1930
1 BW per hr	2000
3 BW per hr	2150
9 BW	2300
11 BW	2330
HFV	2360
2 BW per hr	2695
HFV	2725
HFV	3608