WHEELER	I	I	O. A. SUTTON OIL COMPANY	WICHITA
LEASE	WELL NO.	TEST NO.	COMPANY	DISTRICT

LOCATION SEC. 33-28-1

FIELD Wildcat

COUNTY Sedgwick

STATE Kansas

CONTRACTOR Renfro Drlg. Co.

MUD DATA

Kind Gel.

Weight 10 lbs.-gal.

Viscosity 33 Sec.

Filter Loss 23.4 c. c. Filter Cake 2/32 in.

Est. Gauge Depth Temp. Calc. 100 F°

Time Tool Open 90 minutes

Time Closed In. 20 minutes

Depth BT. Gauge 2784'

BT. P. R. D. No. 291 Blanked Off No

12 Hr. Clock No. 1552

Pressure Readings Field	Office Corrected
Initial Hydro Mud Pressure	1630 p.s.i.
Initial Flow Pres.	13 p.s.i.
Final Flow Pres.	48 p.s.i.
Closed in Pres.	1158 p.s.i.
Final Hydro Mud Pressure	1589 p.s.i.

Halliburton
OIL WELL CEMENTING CO.

HOLE AND TOOL DATA

Total Depth 2795' Casing Perforations Top – Bottom –

Top Packer Depth 2783' Bottom Packer Depth –

Casing or Hole Size 7 7/8" Liner or Rathole Size –

Formation Tested Kansas City

Size Drill Pipe 4½" API FH Size Drill Collars –

Size Bottom Choke 5/8" Size Surface Choke 1"

Size Hook Wall Packer – Size Rings – No. Rings –

Size & Type Wall Packer 6 3/4" ESA No. Packers 1

Size & Length Anchor 4 5/8" x 12'

PRD Device No. 1814 Depth 2791' Blanked Off Yes

REMARKS: Formation tested from 2783' to 2795' in the Kansas City.

Tool opened @ 12:42 A. M. with a weak blow and continued throughout the test, closed in pressure taken @ 2:12 A. M., and started off bottom @ 2:32 A. M. Recovered 15' of mud, and 60' of salt water.

Amount of Cushion None All depths measured from Rotary Table

Date 5-2-56

Ticket No. 38301

HOWCO DISTRICT Winfield

Kind of Job Open Hole Test

Price $215.00

Second Packer Assembly –

Safety Joint –

Extra Folder Charge –

Jars –

Total $215.00


Witnessed By Mr. R. G. Brooks

Tester G. W. McGinnis

No. Folders Reproduced 5

HOWCO 893-R3 25M 199M (Printed in U. S. A.)—Southwestern—4806E

TIME



PRESSURE

Each Horizontal Line Equal to 1000 p.s.i.

WILD CAT WHEELER	I	2	O.A. SUTTON OIL COMPANY	WICHITA
LEASE	WELL NO.	TEST NO.	COMPANY	DISTRICT

LOCATION	SEC. 33-28-1e
FIELD	Wildcat
COUNTY	Sedgwick
STATE	Kansas
CONTRACTOR	Ren Fro Drlg. Co.

MUD DATA

Kind	Starch
Weight	9.8 lbs.-gal.
Viscosity	39 Sec.
Filter Loss	22 c. c. Filter Cake 2/32 in.
Est. Gauge Depth Temp.	Calc. 110 F°
Time Tool Open	60 minutes
Time Closed In.	20 minutes
Depth BT. Gauge	3155'
BT. P. R. D. No.	396 Blanked Off No
12 Hr. Clock No.	2255

Pressure Readings	Field	Office Corrected
Initial Hydro Mud Pressure		1672 p.s.i.
Initial Flow Pres.		11 p.s.i.
Final Flow Pres.		55 p.s.i.
Closed in Pres.		1295 p.s.i.
Final Hydro Mud Pressure		1645 p.s.i.

Halliburton
OIL WELL CEMENTING CO.

HOLE AND TOOL DATA


Total Depth	3219'	Casing Perforations Top	-
		Bottom	-
Top Packer Depth	3160'	Bottom Packer Depth	3166'
Casing or Hole Size	8 5/8"	Liner or Rathole Size	-
Formation Tested	Top Mississippi.		
Size Drill Pipe	4½" API FH	Size Drill Collars	1"
Size Bottom Choke	3/4"	Size Surface Choke	1"
Size Hook Wall Packer	-	Size Rings -	No. Rings -
Size & Type Wall Packer	6 3/4" ESA		No. Packers 1
Size & Length Anchor	4½" x 53'		
PRD Device No.	1982 Depth 3217'	Blanked Off	Yes

Date	5-5-56
Ticket No.	60841
HOWCO DISTRICT	El Dorado
Kind of Job	Straddle Test
Price	$215.00
Second Packer Assembly	75.00
Safety Joint	-
Extra Folder Charge	-
Jars	-
Total	$290.00
Witnessed By	Mr. R. G. Brooks
Tester	Richard

REMARKS: Formation tested from 3166' to 3219' in the Top Mississippi. Tool opened @ 11:30 A. M. with a strong blow and continued throughout the test, closed in pressure taken @ @ 12:30 P. M., and started off bottom @ 12:50 P. M. Recovered 15' of oil, 60' of heavy mud, 30' of light oil cut mud, and 30' of water & mud.

Amount of Cushion none All depths measured from Rotary Bushing No. Folders Reproduced 5

TIME



PRESSURE

Each Horizontal Line Equal to 1000 p.s.i.