


WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY
412 Union National Bk Bldg., Wichita, Kansas

16-28-11E

SELBY OIL & GAS CO.
Wingrave No. 8.

SEC.16 T.28 R.11E
NW SE SW SE
600' N of SL
800' E of WL SE $\frac{1}{4}$

County. Greenwood



Total Depth. 1157'
Comm. 6-15-41 Comp. 7-9-41
Shot or Treated. 1500 Gals. Acid 1145-46
Contractor. Lemons Bros. Drlg. Co.
Issued. 8-30-41 Cable O-1157

CASING:

10" 279' P
8" 467' 8" P
6" 844' (P 114')
5" 1145' LI

Elevation.

Production. Approx. 10 B.

Figures Indicate Bottom of Formations.

surface	5	2BWPH 1065
lime hd gy	15	oil show 1110-17
shale gy sft	18	lime & shale gy 1127
red-bed	38	lime gy 1145
shale gy	63	lime sft brown -oil 1146
shale green	70	lime gy 1157
shale gy	81	Total Depth.
lime gy hd	83	
lime gy med	110	Approximately 10 Bbls
shale blue	112	Settled after 1500 Gals.
lime gy hd	115	Acid
shale dk sft	117	
lime gy hd	119	
shale gy med	140	
lime gy hd	145	
shale sft gy	173	
shale gy med	185	
shale brown med	210	
shale gy med	228	
sand wh med 5 BWPH	245	
lime gy hrd	259	
shale blue	288	
lime	294	
lime gy med	295	
shale dk med	298	
lime	300	
shale	305	shale 591
red rock	335	lime 596
shale blue sft	339	shale 625
lime	352	lime 630
shale blue sft	367	shale 678
lime	370	lime 811
shale	373	wtr at 617 - Increased
red rock	388	to 5 BWPH 715-22
lime	391	shale 960
shale	414	lime 967
too much wtr to		shale 969
bail at 414		lime 974
sand wh hrd	437	shale 1018
sand wh sft	442	lime 1BWPH 1055 1118
shale	562	shale blk 1120
lime	567	