

SELBY OIL & GAS CO.
Wingrave No. 1.

SEC.16 T.28 R.11E
SEc SW 16-28-11E
220'W of EL 220'N of SL SW $\frac{1}{4}$

Total Depth. 1169'
Comm. 3-26-41 Comp. 4-21-41
Shot or Treated.
Contractor. Lemons Bros.Drlg.Co.
Issued. 6-7-41

County. Greenwood



CASING:
10" 7'
8" 470' P
6" 844' P
53/16" 1143' Cem.

Elevation.

Production. Dry

Figures Indicate Bottom of Formations.

shale & lime strks	35
red bed	55
shale & lime	60
red bed	70
shale & lime strks	150
red bed	157
shale & lime strks	238
sand	HFV 250
sand	HFV & caving 260
shale & lime strks	HFV 310
shale blk	HFV 313
lime & shale strks	HFV 322
red rock	HFV 335
red rock	HFV 340
shale	HFV 345
red rock	HFV 355
shale & lime strks	HFV 427
sand	HFV 465
shale & lime strks	745
lime sft, wtr	760
lime sft, oil show	765
lime	830
shale	970
lime med	982
shale	985
shale sdy	1010
shale	1015
lime	1040
lime hrd	1065
lime sft, wtr	1070
lime med	1073
lime sft, wtr	1085
lime med	1090
lime	1129
shale blk	1131
lime sft, odor oil	1134
lime hrd	1135
lime sft, odor oil	1136
lime med	1138
lime & shale broken	1139
lime hrd	1143
lime	1158
shale	1160
lime	1162
lime med	1168
lime sft(12BWP 1168-69)	1169
Total Depth.	