


DERBY OIL CO.  
Davis No. 1.

SEC. 8 T. 28 R. 11 E.  
SE SW NE

8-28-11E

County Greenwood.

Total Depth. 1228 $\frac{1}{2}$   
Comm. 8-7-41 Comp. 8-30-41  
Shot or Treated.  
Contractor. J.R.Fester.  
Issued. 10-18-41



CASING.

8 $\frac{1}{2}$ " 524'  
65/8" 896'  
5 $\frac{1}{2}$ " 1194' cem.

Elevation.

Production. Pot. 38 B.  
no wtr.

Figures Indicate Bottom of Formations.

|              |      |
|--------------|------|
| surface hole | 25   |
| slate        | 30   |
| lime         | 45   |
| shale        | 55   |
| lime         | 60   |
| shale        | 70   |
| lime         | 80   |
| shale        | 85   |
| red rock     | 107  |
| shale        | 130  |
| lime         | 136  |
| shale        | 144  |
| lime         | 150  |
| shale        | 155  |
| lime         | 165  |
| shale        | 178  |
| lime         | 182  |
| slate        | 210  |
| lime         | 215  |
| shale        | 232  |
| lime         | 242  |
| shale        | 268  |
| water sand   | 300  |
| shale        | 338  |
| lime         | 342  |
| slate        | 348  |
| lime         | 363  |
| shale blk    | 368  |
| lime         | 371  |
| shale        | 384  |
| lime         | 390  |
| red rock     | 409  |
| lime         | 434  |
| shale        | 480  |
| sand         | 520  |
| shale        | 570  |
| shale        | 630  |
| lime         | 635  |
| shale        | 655  |
| lime         | 665  |
| shale        | 741  |
| lime         | 892  |
| shale        | 1052 |
| lime         | 1063 |

|              |                    |
|--------------|--------------------|
| shale        | 1070               |
| lime         | 1080               |
| sdv shale    | 1085               |
| red rock     | 1088               |
| slate        | 1100               |
| lime         | 1112               |
| slate        | 1120               |
| lime         | 1130               |
| shale        | 1135               |
| lime         | 1165               |
| sand water   | 1173               |
| lime         | 1191               |
| shale blk    | 1193               |
| lime         | 1194               |
| drilling in  |                    |
| cement plug  | 1174-94            |
| shale        | 1196 $\frac{1}{2}$ |
| lime         | 1210               |
| shale        | 1217               |
| lime         | 1228 $\frac{1}{2}$ |
| Total Depth. |                    |

C.O. and tested  $\frac{1}{2}$  BOPH no time. Gave 500A.  
and 1000 Gal Butane P.O.P. - cleaned out  
and pumped 24 oil in 15 hours, no water.  
N. Pot. 38 bbls oil and no water.

GEOLOGICAL LOG.

|                 |                          |
|-----------------|--------------------------|
| Top Kansas City | 1041.                    |
| S.S.O.          | 1091-94                  |
| Pay             | 1125-28 $\frac{1}{2}$ TD |