

J. H. WAGNER DRILLING COMPANY

COMPANY. Doyle & Leslie
 FARM Stryker WELL NO. 1
 TOTAL DEPTH. 1324
 COMM. 12/20/52 COMP. 1/6/54
 CONTRACTOR: J. H. WAGNER

SEC. 2 TWP. 28 R. 11 E
 DESC. 22 NW SW
 COUNTY Wilson KANSAS
 CASING RECORD:

12 1/2" 89'
 10" 817'
 5 1/2" 1300' Cemented w/46 sec.

ISSUED: 1/14/54 E. Burdick, Esq.

ELEVATION _____ PRODUCTION _____

(FIGURES INDICATE BOTTOM OF FORMATION)

Sand	49	Lime, white	813
Shale	65	Lime, dark gray	823
1/4 BW 60-63		Shale, dark	826
Shale, blue	87	1/4 BW 830-838	
Lime, gray	90	Sandy Lime	838
Shale, blue	100	Shale, black	847
Shale, light	115	Lime, brown	855
Shale, blue	130	Shale, black	857
Lime, white	138	Lime, brown	863
Lime, gray	147	Sandy Lime	870
Shale, light	337	Lime, white	893
Lime, gray	365	Shale, dark	930
Lime, white	400	Shale, light	950
Shale, blue	430	Lime, gray	965
Shale, light	462	Shale, light	977
Lime, gray	492	Lime, gray	979
Shale, light	567	Shale, light	983
Lime, gray	570	Lime	985
Shale, gray	574	Lime, white	993
1 BW 590-598		Shale, sandy	1045
2 BW 605-610		Shale, light	1078
Lime, white	615	Lime, brown	1105
Lime, gray	623	Shale, dark	1128
Sandy Shale	635	Lime, gray	1143
1 1/2 BW 640-648		Shale, black	1148
Sand, gray	650	Lime, gray	1153
Sandy Shale	660	Sandy Shale, light	1178
Lime, gray	666	Sandy Shale, dark	1209
Shale, gray	692	Shale, black	1215
Lime, gray	700	Shale, gray	1220
Lime, white	705	Shale, dark	1228
Lime	715	Lime, gray	1238
1 1/2 BW 715-722		Shale, light	1246
Lime, brown	740	Shale, gray	1255
1 1/2 BW 746-752		Lime, brown	1258
Lime, gray	750	Shale, dark	1263
Straightening hole 743-754		Shale, gray	1270
Lime, brown	759	Shale, light	1285
Lime, dark gray	768	Shale & Shells	1293
Lime, brown	774	Sand, brown	1305
Lime, white	781	Sand	1321
Shale, black	788	Shale, black	1324
Sandy Shale	800		
Sandy Lime, white	809		
Shale, black	811		

Cored 1311-1324
 PB to 1300 SL