

# OILFIELD RESEARCH LABORATORIES

536 NORTH HIGHLAND - CHANUTE, KANSAS 66720 - PHONE (316) 431-2650

April 30, 1980

TECH American Kansas, Incorporated  
P.O. Box 467  
Moran, Kansas 66755

Gentlemen:


Attached hereto are the results of tests run on the rotary core taken from the Scott Lease, Well No. 3, located 1190' from North Line and 150' from East Line, Section 3, T-28S, R-15E, Wilson County, Kansas.

The core was sampled and sealed in plastic bags by a representative of the client, and submitted to our laboratory on April 23, 1980.

Your business is greatly appreciated.

Very truly yours,

OILFIELD RESEARCH LABORATORIES



Sanford A. Michel

SAM/tem

5 c to Moran, Kansas

OILFIELD RESEARCH LABORATORIES

LOG

Name TECH American Kansas, Inc. Lease Scott Well No. 3

Depth Interval,  
Feet

Description

BARTLESVILLE SAND

1019.0 - 1022.6

Dark brown sandstone.

1022.6 - 1023.7

Dark brown slightly shaly sandstone.

1023.7 - 1027.8

Dark brown sandstone.

1027.8 - 1028.3

Dark brown shaly sandstone.

**Oilfield Research Laboratories**

**RESULTS OF SATURATION & PERMEABILITY TESTS**

**TABLE 1**

Company TECH American Kansas, Incorporated Lease Scott Well No. 3

Sample No.	Depth, Feet	Porosity Percent	Percent Saturation			Oil Content Bbls. / A Ft.	Perm., Mill.
			Oil	Water	Total		
1	1019.5	19.9	35	30	65	540	20.
2	1020.4	18.9	35	31	66	513	32.
3	1021.3	15.9	29	43	72	358	17.
4	1022.5	19.9	26	38	64	401	65.
5	1023.5	19.2	25	39	64	372	8.2
6	1024.3	18.1	28	37	65	393	17.
7	1025.5	19.0	35	26	61	516	45.
8	1026.5	19.5	43	25	68	651	104.
9	1027.5	21.3	37	27	64	611	13.
10	1028.2	18.8	35	35	70	511	2.0