

OILFIELD RESEARCH LABORATORIES

536 NORTH HIGHLAND - CHANUTE, KANSAS 66720 - PHONE (316) 431-2650

September 17, 1980

JEB Oil Company
209 South Fourth
Neodesha, Kansas 66757

Gentlemen:


Attached hereto are the results of tests run on the rotary core taken from the Short Lease, Well No. 1, Wilson County, Kansas and submitted to our laboratory on September 6, 1980.

The core was sampled by a representative of Oilfield Research Laboratories after it was received in the laboratory.

Your business is greatly appreciated.

Very truly yours,

OILFIELD RESEARCH LABORATORIES



Sanford A. Michel

SAM/ks

5 c to Neodesha, Kansas

OILFIELD RESEARCH LABORATORIES

LOGName JEB Oil Company Lease Short Well No. 1

<u>Depth Interval,</u> <u>Feet</u>	<u>Description</u>
	<u>LOWER BARTLESVILLE SAND</u>
1008.0 - 1012.1	Gray laminated sandstone and shale.
1012.1 - 1015.2	Gray carbonaceous very shaly sandstone.
1015.2 - 1017.0	Gray laminated sandstone and shale.
1017.0 - 1018.2	Gray and light brown laminated sandstone and shale.
1018.2 - 1019.5	Gray laminated sandstone and shale.

Oilfield Research Laboratories

RESULTS OF SATURATION & PERMEABILITY TESTS

TABLE 1

Company JEB Oil Company Lease Short Well No. 1

Sample No.	Depth, Feet	Porosity Percent	Percent Saturation			Oil Content Bbla. / A Ft.	Perm., Mill.
			Oil	Water	Total		
1	1012.5	14.5	54	26	80	608	Imp.
2	1013.5	13.7	57	31	88	606	Imp.
3	1014.5	14.0	47	20	67	511	Imp.
4	1017.5	14.1	33	53	86	361	Imp.