

2 ✓

LOG OF SPRINGER OIL WELL No. 1

Drilled for: W.F. Callahan, Jr., M.D., et al

Contractors: Barrett S. Faulkner  
Route #1 Box 199  
Cherokee, Kansas.

Drilling Commenced: June 8, 1953

Finished Drilling: June 17, 1953  
Completed Well : June 23, 1953

LOCATION: Sec. 34-28-16 Wilson County, Kansas.

Feet	Description	Total Depth	Remarks
1	Soil	1	
11	Clay	12	
5	Shale	17	Set 17' of 6 1/2" Drive Pipe
6	Line	23	
12	Shale	35	
20	Sand	55	1/2" Bailer Water 85' - 90'
27	Shale	82	
3	Line	85	
35	Shale	120	
107	Line	217	
3	Shale No.	220	Water - Hole Full
11	Line	231	
3	Shale	234	
32	Line	316	
65	Shale	411	Run 243' of 6 1/2" casing
24	Line	435	Little gas at 300'
11	Shale	446	
11	Line	457	
10	Sand	467	
23	Shale	490	
21	Sand	510	
27	Shale	537	
37	Line	574	
14	Shale	608	S.L. No
23	Line	631	80 Feet
6	Shale No.	637	10 Baffles Water per hour 620-63
4	Line	641	
25	Shale	666	
1	OIL Sand	667	
1	OIL Sand	668	Shale Oil - Dead
1	OIL Sand	669	Good OIL sand - a little shaly
<b>TOTAL DEPTH</b>		<b>669'</b>	

865  
628  
237

June 17, 1953 - Ran 662' - New 2 1/2" tubing  
- Packer bet 8 662'  
- Sealing Slits 661'  
- Ran 15 Baffles 62' on well

June 19, 1953 - Plugged well and pulled 6 1/2" casing  
June 23, 1953 - Ran 1" Pipe in well and pumped with rig A hours