

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION

Form ACO-1
September 1999
Form Must Be Typed

WELL COMPLETION FORM
WELL HISTORY - DESCRIPTION OF WELL & LEASE

Operator: License # 32606
Name: Devon Energy Production Company, L.P.
Address: 20 North Broadway, Suite 1500 Attn: Robert Cole
City/State/Zip: Oklahoma City, OK 73102-8260
Purchaser: Tall Grass, LLC
Operator Contact Person: Robert Cole
Phone: (405) 235-3611 **RECEIVED**
Contractor: Name: McPherson Drlg. **OCT 27 2003**
License: #5675 **KCC WICHITA**
Wellsite Geologist: Dave Fleming

Designate Type of Completion:
 New Well Re-Entry Workover
 Oil SWD SLOW Temp. Abd.
 Gas ENHR SIGW
 Dry Other (Core, WSW, Expl., Cathodic, etc)

If Workover/Re-entry: Old Well Info as follows:
Operator: _____
Well Name: _____

Original Comp. Date: _____ Original Total Depth: _____
 Deepening Re-perf. Conv. to Enhr./SWD
 Plug Back Plug Back Total Depth
 Commingled Docket No. _____
 Dual Completion Docket No. _____
 Other (SWD or Enhr.?) Docket No. _____

<u>6/24/03</u> Spud Date	<u>6/26/03</u> TD	<u>8/26/03</u>
Spud Date or Recompletion Date	Date Reached TD	Completion Date or Recompletion Date

API No. 15 - 133-25920
County: Neosho
_____ - nw Sec. 28 Twp. 28 S. R. 18 East West
1800 feet from S (circle one) Line of Section
2300 feet from E (circle one) Line of Section

Footages Calculated from Nearest Outside Section Corner:
(circle one) NE SE NW SW
Lease Name: Robert Kopley 28 Well #: 1
Field Name: _____
Producing Formation: Cherokee Coal
Elevation: Ground: 968 ft. Kelly Bushing: _____
Total Depth: 1,246 ft. Plug Back Total Depth: 1,199 ft.
Amount of Surface Pipe Set and Cemented at 24 Feet
Multiple Stage Cementing Collar Used? Yes No
If yes, show depth set _____ Feet
If Alternate II completion, cement circulated from Surface
feet depth to 1,206' w/ 170 sx cmt.

Drilling Fluid Management Plan
(Data must be collected from the Reserve Pit)
Chloride content N/A ppm Fluid volume N/A bbls
Dewatering method used _____
Location of fluid disposal if hauled offsite: _____
Operator Name: _____
Lease Name: _____ License No.: _____
Quarter _____ Sec. _____ Twp. _____ S. R. _____ East West
County: _____ Docket No.: _____

INSTRUCTIONS: An original and two copies of this form shall be filed with the Kansas Corporation Commission, 130 S. Market - Room 2078, Wichita, Kansas 67202, within 120 days of the spud date, recompletion, workover or conversion of a well. Rule 82-3-130, 82-3-106 and 82-3-107 apply. Information of side two of this form will be held confidential for a period of 12 months if requested in writing and submitted with the form (see rule 82-3-107 for confidentiality in excess of 12 months). One copy of all wireline logs and geologist well report shall be attached with this form. ALL CEMENTING TICKETS MUST BE ATTACHED. Submit CP-4 form with all plugged wells. Submit CP-111 form with all temporarily abandoned wells.

All requirements of the statutes, rules and regulations promulgated to regulate the oil and gas industry have been fully complied with and the statements herein are complete and correct to the best of my knowledge.

Signature: Robert Cole
Title: Sr. Eng. Tech Date: 10/22/03
Subscribed and sworn to before me this 23rd day of October, 2003
Notary Public: Patti Diechers
Date Commission Expires: 1-10-2004
#0000586 in Oklahoma County, OK

KCC Office Use ONLY
 Letter of Confidentiality Attached
If Denied, Yes Date: _____
 Wireline Log Received
 Geologist Report Received
 UIC Distribution

Operator Name: Devon Energy Production Company, L.P. Lease Name: Robert Kepley 28 Well #: 1
 Sec. 28 Twp. 28 S. R. 18 East West County: Neosho

INSTRUCTIONS: Show important tops and base of formations penetrated. Detail all cores. Report all final copies of drill stems tests giving interval tested, time tool open and closed, flowing and shut-in pressures, whether shut-in pressure reached static level, hydrostatic pressures, bottom hole temperature, fluid recovery, and flow rates if gas to surface test, along with final chart(s). Attach extra sheet if more space is needed. Attach copy of all Electric Wireline Logs surveyed. Attach final geological well site report.

Drill Stem Tests Taken <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No <i>(Attach Additional Sheets)</i> Samples Sent to Geological Survey <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No Cores Taken <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No Electric Log Run <input checked="" type="checkbox"/> Yes <input type="checkbox"/> No <i>(Submit Copy)</i> List All E. Logs Run: GR, N, D, DIL	<input checked="" type="checkbox"/> Log Formation (Top), Depth and Datum <input checked="" type="checkbox"/> Sample Name Top Datum See Attachments <div style="text-align: center; font-weight: bold; font-size: 1.2em;"> RECEIVED OCT 27 2003 KCC WICHITA </div>
---	--

CASING RECORD <input checked="" type="checkbox"/> New <input type="checkbox"/> Used							
Report all strings set-conductor, surface, intermediate, production, etc.							
Purpose of String	Size Hole Drilled	Size Casing Set (In O.D.)	Weight Lbs./ Ft.	Setting Depth	Type of Cement	# Sacks Used	Type and Percent Additives
Surface	11"	8 5/8"	32 #/ft	24'	Portland	4	none
Production	7 7/8"	5 1/2"	14 #/ft	1,206'	CI 'A'	170	ThickSet

ADDITIONAL CEMENTING / SQUEEZE RECORD				
Purpose:	Depth Top Bottom	Type of Cement	#Sacks Used	Type and Percent Additives
<input type="checkbox"/> Perforate				
<input type="checkbox"/> Protect Casing				
<input type="checkbox"/> Plug Back TD				
<input type="checkbox"/> Plug Off Zone				

Shots Per Foot	PERFORATION RECORD - Bridge Plugs Set/Type Specify Footage of Each Interval Perforated	Acid, Fracture, Shot, Cement Squeeze Record <i>(Amount and Kind of Material Used)</i>	Depth
4 spf	1,052'-1,054', 1,043'-1,048' Riverton	500gIFeHCL, Frac535Bbbs2,800lbs20/40Sd.	
4 spf	987'-989', 981'-984' Rowe, 885'-889' Bluejacket	500gIFeHCl, Frac535Bbbs3,600lbs20/40Sd.	
4 spf	775'-779' Flemng, 737'-741' Crwbrg, 714'-717' Bevier	500gIFeHCl, Frac602Bbbs4,500lbs20/40Sd.	
4 spf	640'-646' Mulky, 628'-634' Summit	500gIFeHCl, Frac625Bbbs5,000lbs20/40Sd.	

TUBING RECORD		Size 2 3/8"	Set At 1,138'-EOT	Packer At N/A	Liner Run <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No
Date of First, Resumed Production, SWD or Enhr. 10/17/03			Producing Method <input checked="" type="checkbox"/> Flowing <input checked="" type="checkbox"/> Pumping <input type="checkbox"/> Gas Lift <input type="checkbox"/> Other (Explain)		
Estimated Production Per 24 Hours	Oil Bbbs. N/A	Gas Mcf 10 Mcfd	Water Bbbs. 300 bwpd	Gas-Oil Ratio N/A	Gravity N/A

Disposition of Gas METHOD OF COMPLETION Production Interval

Vented Sold Used on Lease
 Open Hole Perf. Dually Comp. Commingled
(If vented, Sumit ACO-18.)
 Other (Specify) _____