

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION

Form ACO-1
September 1999
Form Must Be Typed

WELL COMPLETION FORM

WELL HISTORY - DESCRIPTION OF WELL & LEASE

* Completion date
Rec'd this on
5/16/02

Operator: License # 32845
Name: Devon SFS Operating Inc.
Address: 20 North Broadway, Suite 1500
City/State/Zip: Oklahoma City, OK 73102-8260
Purchaser: Tall Grass, LLC
Operator Contact Person: Robert Cole
Phone: (405) 235-3611
Contractor: Name: McPherson Drlg.
License: #5675
Wellsite Geologist: Harley Gilbert

RECEIVED
OCT 20 2003
KCC WICHITA

Designate Type of Completion:
 New Well Re-Entry Workover
 Oil SWD SIOW Temp. Abd.
 Gas ENHR SIGW
 Dry Other (Core, WSW, Expl., Cathodic, etc)

If Workover/Re-entry: Old Well Info as follows:
Operator: _____
Well Name: _____

Original Comp. Date: _____ Original Total Depth: _____
 Deepening Re-perf. Conv. to Enhr./SWD
 Plug Back Plug Back Total Depth
 Commingled Docket No. _____
 Dual Completion Docket No. _____
 Other (SWD or Enhr.?) Docket No. _____

1/8/02 Spud Date 1/9/02-TD * 9/2/03
Spud Date or Date Reached TD ~~Completion Date~~
Recompletion Date Recompletion Date

API No. 15 - 133-25804 - 0001
County: Neosho
SW Sec. 29 Twp. 28 S. R. 18 East West
500 feet from S / N (circle one) Line of Section
1800 feet from E / W (circle one) Line of Section
Footages Calculated from Nearest Outside Section Corner:
(circle one) NE SE NW SW
Lease Name: J. Carroll Finley 29 Well #: 1

Field Name: _____
Producing Formation: Cherokee Coals
Elevation: Ground: 970 ft. Kelly Bushing: _____
Total Depth: 1,157 ft. Plug Back Total Depth: 1,144 ft.
Amount of Surface Pipe Set and Cemented at _____ Feet
Multiple Stage Cementing Collar Used? Yes No
If yes, show depth set _____ Feet
If Alternate II completion, cement circulated from Surface
feet depth to 1,151 ft. w/ 165 _____ sx cmt.

Drilling Fluid Management Plan
(Data must be collected from the Reserve Pit)
Chloride content N/A ppm Fluid volume N/A bbls
Dewatering method used _____
Location of fluid disposal if hauled offsite: _____
Operator Name: _____
Lease Name: _____ License No.: _____
Quarter _____ Sec. _____ Twp. _____ S. R. _____ East West
County: _____ Docket No.: _____

INSTRUCTIONS: An original and two copies of this form shall be filed with the Kansas Corporation Commission, 130 S. Market - Room 2078, Wichita, Kansas 67202, within 120 days of the spud date, recompletion, workover or conversion of a well. Rule 82-3-130, 82-3-106 and 82-3-107 apply. Information of side two of this form will be held confidential for a period of 12 months if requested in writing and submitted with the form (see rule 82-3-107 for confidentiality in excess of 12 months). One copy of all wireline logs and geologist well report shall be attached with this form. ALL CEMENTING TICKETS MUST BE ATTACHED. Submit CP-4 form with all plugged wells. Submit CP-111 form with all temporarily abandoned wells.

All requirements of the statutes, rules and regulations promulgated to regulate the oil and gas industry have been fully complied with and the statements herein are complete and correct to the best of my knowledge.

Signature: Robert Cole
Title: Sr. Eng. Tech. Date: 10/14/03
Subscribed and sworn to before me this 15th day of October
2003
Notary Public: Kim Walker
Date Commission Expires: 12/8/05

KCC Office Use ONLY
 Letter of Confidentiality Attached
If Denied, Yes Date: _____
 Wireline Log Received
 Geologist Report Received
 UIC Distribution

Operator Name: Devon SFS Operating Inc. Lease Name: J. Carroll Finley 29 Well #: 1
 Sec. 29 Twp. 28 S. R. 18 East West County: Neosho

INSTRUCTIONS: Show important tops and base of formations penetrated. Detail all cores. Report all final copies of drill stems tests giving interval tested, time tool open and closed, flowing and shut-in pressures, whether shut-in pressure reached static level, hydrostatic pressures, bottom hole temperature, fluid recovery, and flow rates if gas to surface test, along with final chart(s). Attach extra sheet if more space is needed. Attach copy of all Electric Wireline Logs surveyed. Attach final geological well site report.

Drill Stem Tests Taken Yes No
 (Attach Additional Sheets)

Samples Sent to Geological Survey Yes No

Cores Taken Yes No

Electric Log Run Yes No
 (Submit Copy)

List All E. Logs Run:

GR, N, D, DIL, CBL

Log Formation (Top), Depth and Datum Sample

Name Top Datum

See Attachments

RECEIVED
OCT 20 2003
KCC WICHITA

CASING RECORD <input type="checkbox"/> New <input type="checkbox"/> Used							
Report all strings set-conductor, surface, intermediate, production, etc.							
Purpose of String	Size Hole Drilled	Size Casing Set (In O.D.)	Weight Lbs. / Ft.	Setting Depth	Type of Cement	# Sacks Used	Type and Percent Additives
Surface	11"	8 5/8"	32 #/ft	20'	Portland	4	none
Production	7 7/8"	5 1/2"	14 #/ft	1,151'	Cl 'A'	165	ThickSet

ADDITIONAL CEMENTING / SQUEEZE RECORD				
Purpose:	Depth Top Bottom	Type of Cement	#Sacks Used	Type and Percent Additives
<input type="checkbox"/> Perforate <input type="checkbox"/> Protect Casing <input type="checkbox"/> Plug Back TD <input type="checkbox"/> Plug Off Zone				

Shots Per Foot	PERFORATION RECORD - Bridge Plugs Set/Type Specify Footage of Each Interval Perforated	Acid, Fracture, Shot, Cement Squeeze Record (Amount and Kind of Material Used)	Depth
4 spf	1,045'-1,048' Riverton, 1,003'-07', 1,016'-19' Rowe CIBP @ 980'w/1 sk cmt.	500 gls FeHCl, Frac 36,500gls, 3600#20/40	
4 spf	906'-909' Bluejacket, 883'-886' Weir	500gls FeHCl, Frac 450Bbls, 3,100lbs 20/40 Sd	
4 spf	786'-790' Flemming, 722'-726' Bevier	500gls FeHCl, Frac 440Bbls, 4,400lbs 20/40 Sd	
4 spf	651'-655' Mulky, 639'-642' Summit	500gls FeHCl, Frac 500Bbls, 1,700lbs 20/40 Sd.	

TUBING RECORD	Size	Set At	Packer At	Liner Run
	2 3/8"	942'-EOT	N/A	<input type="checkbox"/> Yes <input checked="" type="checkbox"/> No

Date of First, Resumed Production, SWD or Enhr.	Producing Method
10/9/03	<input checked="" type="checkbox"/> Flowing <input checked="" type="checkbox"/> Pumping <input type="checkbox"/> Gas Lift <input type="checkbox"/> Other (Explain)

Estimated Production Per 24 Hours	Oil Bbls.	Gas Mcf	Water Bbls.	Gas-Oil Ratio	Gravity
	N/A	26 Mcfd	80 bwpd	N/A	N/A

Disposition of Gas: Vented Sold Used on Lease (If vented, Sumit ACO-18.)

METHOD OF COMPLETION: Open Hole Perf. Dually Comp. Commingled Other (Specify)

Production Interval: _____