

Company: CREEK OIL & GAS CO., INC.
 Lease: Wells
 Well No. 10

Location: 1855' FEL & 1770' FNL
 Section 27, T. 28S, R. 18E
 County: Neosho State Kansas

Contractor: J. W. Fisher
 Commenced: October 9, 1957
 Drilling Completed:
 Well Completed: October 21, 1957

Elevation: 975'
 Total Depth: 838' PB: 811'
 I. P.: Oil
 Zone Completed: Bartlesville ss
 Method Compl.:
 Packer set @ 799'

Casing Record:
 20" 6 5/8" 640' (Pulled)
 15 1/2" 5 3/16"
 12 1/2" 4 1/2"
 10" 2" 799' cem w/ 25 sx
 8 1/4" 1"

Ft. of Strata	Fm.	Bot. Fm.
3	Sand & Clay	3
7	Sandstone	10
35	Shale	45
5	Limestone	50
20	Shale	70
5	Limestone	75
15	Shale- light	90
65	Limestone	155
36	Limestone- shells	191
9	Shale	200
40	Limestone	240
18	Shale- black	250
5	Limestone	255
4	Shale- gas	259
49	Limestone	308
30	Shale	338
6	Limestone- shells	344
26	Shale	370
15	Limestone	385
15	Shale	400
8	Limestone	408
77	Shale- light	485
51	Limestone	536
45	Shale	581
23	Limestone S.L.M.	604
10	Shale- dark	614
5	Limestone	619
156	Shale	775
22	Shale- sandy	797
CORED @ 792'		
6 1/2	Sandstone- oil, few shale streaks	803 1/2
2	Shale- sandy	805 1/2
6	Sandstone- oil, few shale streaks	811 1/2
9	Shale- sandy	820 1/2
4	Sandstone	824 1/2
4	Shale- sandy	828 1/2
9 1/2	Shale- dark	838

Ft. of Strata	Fm.	Bot. Fm.
---------------	-----	----------

LOG TOPS:

Pawnee ls	485'
Labette	536'
Ft. Scott ls	581'
Cherokee sh	619'
Bartlesville	797'

TOTAL DEPTH: 838'

