

Company: CREEK OIL & GAS CO., INC.
Lease: Wells
Well No. 7

Location: 1755' FWL & 1670' FNL
Section 27, T. 28S, R. 18E
County: Neosho State Kansas

Contractor: J. W. Fisher
Commenced: August 26, 1957
Drilling Completed:
Well Completed: September 4, 1957
Casing Record:

Elevation: 984'
Total Depth: 840'
I. P.: Oil
Zone Completed: Bartlesville ss
Method Compl.:

20"	6 5/8"	660'	(Pulled)
15 1/2"	5 3/16"		
12 1/2"	4 1/2"	839'	cem w/ 45 sx
10"	2"		
8 1/4"	1"		

<u>Ft. of</u>		<u>Bot.</u>
<u>Strata</u>	<u>Fm.</u>	<u>Fm.</u>
1	Soil	1
8	Sandstone & Clay	9
72	Shale	81
6	Limestone	87
18	Shale	105
65	Limestone	170
48	Shale	218
19	Limestone	237
5	Shale	242
12	Limestone	254
14	Shale- black	268
54	Limestone	322
25	Shale	347
5	Limestone- shells	352
31	Shale	383
12	Limestone- shells	395
16	Shale	411
12	Limestone	423
77	Shale	500
53	Limestone	553
44 1/2	Shale	597 1/2
20 1/2	Limestone	618
17	Shale	635
4	Limestone	639
37	Shale	676
3	Limestone	679
46	Shale- dark	725
2	Limestone	727
51	Shale	778
1	Limestone	779
20	Shale- sandy	799
CORED @ 796'		
29	Sandstone- oil, few shale streaks	828
12	Shale- w/ carb. ss.	840

TOTAL DEPTH: 840'

<u>Ft. of</u>		<u>Bot.</u>
<u>Strata</u>	<u>Fm.</u>	<u>Fm.</u>

LOG TOPS:

Pawnee ls	500'
Labette	553'
Ft. Scott ls	597 1/2'
Cherokee sh	629'
Bartlesville	799'