

Creek Oil & Gas Co., Inc.

T. 28 R. 18E Sec. 27

WELL RECORD

Well No. 6

Wells Farm

Sec. Township

Range County Neosho

State Kansas

**J. W. FISHER
DRILLING CONTRACTOR**

Phone 2843-J

CHANUTE, KANSAS

— FULLY INSURED —

Township Range County

NORTH					
6	5	4	3	2	1
7	8	9	10	11	12
18	17	16	15	14	13
19	20	21	22	23	24
30	29	28	27	26	25
31	32	33	34	35	36
SOUTH					

WEST EAST

E1 981

OIL WELL DATA

Location

Commenced Spudding Aug. - 16 - 1957

Drilling Completed

Well Completed Aug. - 24 - 19573" Rotary cut from 791.20 to 837.70

Date Shot

Torpedo Co.

Shooter

From to shell qts.....

From to shell qts.....

From to shell qts.....

From to shell qts.....

Packer set at ft.

Cemented with 50 sacks of cement

..... lbs. of sand.

Drive Pipe 8' of 10"Casing 651 ft. of 6 1/4"Casing 836.8' of 4 1/2"

Tubing

Top producing sand

Bottom producing sand

Total depth of well 837.70

REMARKS:

No. Feet Strata	Formation	Depth of Hole
2	Sail	2
3	Sandy clay	5
7	Sand rock	12
88	shale	100
62	lime	162
4	shale - black sandy	166
9	lime	175
30	sand - Dark gray	205
10	shale - Gray	215
15	lime	230
5	shale - Grey	235
12	lime	247
16	slate + sand	263
52	lime	315
25	shale - Dark	340
35	shale - light	375
20	sand	395
13	shale	408
8	lime	416
32	shale - light	448
22	shale - Dark	470
24	shale - light	494

No. Feet Strata	Formation	Depth of Hole
51	lime - 40 ft.	545
13	shale - Dark	558
33	shale - light	591
21	lime - 20 ft.	612
9	shale - black	621
4	lime 5 ft.	625
20	shale - sandy	645
20	shale - light	665
7	shale	672
4	lime	676
41	shale	717
2	lime	719
41	shale - dark	760
12	shale - light	772
1	lime	773
7	shale - light	780
7	shale - light sandy	787
4	shale - sandy - Show oil	791

No. Feet Strata	Formation	Depth of Hole
Started Coring at		791 ²⁰ / ₁₀₀
By Von der Veld		
5	Shale - sandy - Shou Oil	796 ³⁰ / ₁₀₀
	Shale - Br. sh.	797 ⁶⁰ / ₁₀₀
	Good fm. Oil sand	821
	Carbon black sand	831 ⁶⁰ / ₁₀₀
	(Leaking Oil - ...)	
	Black sand & shale	837 ⁷⁰ / ₁₀₀
	Reamed Core hole from 791 ²⁰ / ₁₀₀	
	to 837 ⁷⁰ / ₁₀₀	
	Cleaned out Cavings	
	Ran 836.8' of 4 ¹ / ₂ " OD Casing	
	Ran 3 Centralizers 1 each on	
	1st, 3rd & 5th Collars	
	Pulled 651' of 6 ¹ / ₄ " Casing	
	Consolidated Cemented 4 ¹ / ₂ " Casing	
	With 50 sacks Cement	
	Measurements taken 14 inches	
	Above ground level.	

[illegible]

DRILLERS

Stanley Lendine

J. T. Fogleman

Kenneth Shultz

TOOL DRESSERS

Jack Moran

Lewis Fogleman

Bill Leroy