

Company: CREEK OIL & GAS CO., INC.  
Lease: Wells  
Well No. 6

Location: 2200' FWL & 1765' FNL  
Section 27, T. 28S, R. 18E  
County: Neosho State Kansas

Contractor: J. W. Fisher  
Commenced: August 16, 1957  
Drilling Completed:  
Well Completed: August 24, 1957

Elevation: 981'  
Total Depth: 837'  
I. P.: Oil  
Zone Completed: Bartlesville ss  
Method Compl.: Reamed core hole from 791' to 837'. Ran 3 centralizers 1 each on 1st, 3rd, & 5th Collars. Measurements taken 14 inches above ground level.

Casing Record:  
20" 6 5/8" 651' Pulled  
15 1/2" 5 3/16"  
12 1/2" 4 1/2" 837' w/50 sx. cem.  
10" 8" 2"  
8 1/4" 1"

| Ft. of Strata | Fm.                  | Bot. Fm. |
|---------------|----------------------|----------|
| 2             | Soil                 | 2        |
| 3             | Sandy clay           | 5        |
| 7             | Sand rock            | 12       |
| 88            | Shale                | 100      |
| 62            | Lime                 | 162      |
| 4             | Shale, black-sandy   | 166      |
| 9             | Lime                 | 175      |
| 30            | Sand, dark gray      | 205      |
| 10            | Shale - gray         | 215      |
| 15            | Lime                 | 230      |
| 5             | Shale 0 gray         | 235      |
| 12            | Lime                 | 247      |
| 16            | Shale & sand         | 263      |
| 52            | Lime                 | 315      |
| 25            | Shale - dark         | 340      |
| 35            | Shale - light        | 375      |
| 20            | Sand                 | 395      |
| 13            | Shale                | 408      |
| 8             | Lime                 | 416      |
| 32            | Shale - light        | 448      |
| 22            | Shale - dark         | 470      |
| 24            | Shale - light        | 494      |
| 51            | Lime                 | 545      |
| 13            | Shale - dark         | 558      |
| 33            | Shale - light        | 591      |
| 21            | Lime                 | 612      |
| 9             | Shale - black        | 621      |
| 4             | Lime                 | 625      |
| 20            | Shale - sandy        | 645      |
| 20            | Shale - light        | 665      |
| 7             | Shale                | 672      |
| 4             | Lime                 | 676      |
| 41            | Shale                | 717      |
| 2             | Lime                 | 719      |
| 41            | Shale - dark         | 760      |
| 12            | Shale - light        | 772      |
| 1             | Lime                 | 773      |
| 7             | Shale - light        | 780      |
| 7             | Shale - lt. sandy    | 787      |
| 4             | Shale-sandy-show oil | 791      |
| CORED @ 791'  |                      |          |
| 5             | Shale-sandy-show oil | 796      |
| 7             | ss-Broken, oil       | 803      |
| 4             | Shale                | 807      |
| 24            | ss - oil             | 831      |
| 1             | ss - broken          | 832      |
| 1             | ss - shaley          | 833      |
| 1             | Shale, sandy         | 834      |
| 3             | ss - carb. & congl.  | 837      |

| Ft. of Strata | Fm. | Bot. Fm. |
|---------------|-----|----------|
|---------------|-----|----------|

LOG TOPS:

|              |      |
|--------------|------|
| Pawnee ls    | 494' |
| Labette      | 545' |
| Ft. Scott ls | 591' |
| Cherokee sh  | 625' |
| Bartlesville | 796' |

TOTAL DEPTH: 837'