

Company: CREEK OIL & GAS CO., INC.
Lease: Wells
Well No. I-1

Location: 1995' FNL & 2120' FEL
Section 27, T. 28S, R. 18E
County: Neosho State Kansas

Contractor: Cogeco Drilling Co.
Commenced: January 8, 1958
Drilling Completed: January 13, 1958
Well Completed:

Elevation:
Total Depth: 821'
I. P.: Water Injection Well
Zone Completed: Bartlesville ss.
Method Compl.:

Casing Record:
20" 6 5/8"
15 1/2" 5 3/16"
12 1/2" 4 1/2"
10" 2" 790'
8 1/4" 1"

Ft. of Strata	Fm.	Bot. Fm.
3	Soil	3
80	Shale	83
50	Limestone	133
63	Shale	196
18	Limestone	214
10	Shale	224
7	Limestone	231
26	Shale- w/ ls. stks.	257
45	Limestone	302
95	Shale	397
7	Limestone	404
75	Shale	479
5	Limestone	484
16	Shale- w/ ls. stks.	500
33	Limestone	533
42	Shale	575
21	Limestone	596
9	Shale	605
5	Limestone	610
94	Shale	704
2	Limestone	706
84	Shale	790
4	Sandstone	794
CORED @ 794'		
24	Sandstone- oil	818
3	Shale	821

Ft. of Strata	Fm.	Bot. Fm.
---------------	-----	----------

LOG TOPS:

Pawnee ls	500'
Labette	533'
Ft. Scott ls	575'
Cherokee sh	610'
Bartlesville	790'

TOTAL DEPTH: 821'

