

Creek Oil & Gas Co., Inc.

WELL RECORD

Well No. 10

Wells Farm

Sec. 27 Township 28

Range 18E County Neosho

State Kansas

J. W. FISHER
DRILLING CONTRACTOR

Phone 2843-J

CHANUTE, KANSAS

— FULLY INSURED —

Township ----- Range -----
----- County

	NORTH						
	6	5	4	3	2	1	
	7	8	9	10	11	12	
WEST	18	17	16	15	14	13	
	19	20	21	22	23	24	
	30	29	28	27	26	25	
	31	32	33	34	35	36	
	SOUTH						
	EAST						

E1 975

OIL WELL DATA

Location

Commenced Spudding Oct. 9- 1957

Drilling Completed

Well Completed Oct. - 21- 1957

3" Rotary cut from 792' to 838'

Date Shot

Torpedo Co.

Shooter

From to shell qts.....

From to shell qts.....

From to shell qts.....

From to shell qts.....

Packer set at 799' ft.

Cemented with 25 sacks of cement

..... lbs. of sand.

Drive Pipe 24' of 7"

Casing 640 ft. of 6 1/4"

Casing

Tubing 799' of 2"

Top producing sand

Bottom producing sand

Total depth of well 838

REMARKS:

plugged back to 811'

No. Feet Strata	Formation	Depth of Hole
3	Sand & Clay	3
7	Sand rock	10
35	shale	45
5	lime	50
20	shale - light	70
5	lime	75
15	shale - light	90
65	lime	155
36	lime shells	191
9	shale - dark - 2-B-W	200
40	lime	240
5	shale - dark - 4-B-W	245
5	Black slate	250
5	lime	255
4	shale - Gas	259
49	lime	308
12	shale - black	320
18	shale - dark	338
6	lime shells	344
26	shale - light	370
15	lime shells	385
15	shale	400

No. Feet Strata	Formation	Depth of Hole
8	lime	408
77	shale - light	485
51	lime - 40 ft.	536
4	shale - light	540
11	shale - dark	551
30	shale - light	581
23	lime - 20 ft. S.L.M.	604
10	shale - dark	614
5	lime	619
4	shale - dark	623
12	shale - sandy - white	635
25	shale - light	660
35	shale - dark	695
20	shale - light	715
5	shale - dark	720
10	shale - light	730
20	shale - dark	750
25	shale - light	775
17	shale - sandy	792'

DRILLERS

Stanley Lindine

J. T. Fogleman

TOOL DRESSERS

Jack Moran

Lewis Fogleman