


Company - BEECH AIRCRAFT CORP.
Farm - Doyle No. 1.

SEC. 5 T. 28 R. 2 E
NWc NE

Total Depth. 3454'
Comm. 8-29-44 Comp. 10-24-44
Shot or Treated.
Contractor.
Issued. 11-18-44

County, Sedgwick
KANSAS



CASING:
15 1/2" 113' 6" 3060'
12 1/2" 1200' 5" 3347'
8" 2655'

Elevation. _____

Production. Dry

Figures Indicate Bottom of Formations.

cellar & mud, red	25	lime	1035	shale shelly	2295
clay yellow	60	shale	1055	shale	2400
mud blue	65	lime	1060	lime	2410
lime	80	shale	1080	shale	2550
shale	90	lime	1085	lime(wtr 2630-50)	2630
lime	100	shale	1145	lime sdy	2650
shale	105	sand	1150	lime	2730
lime	118	shale	1160	shale	2733
shale	125	lime	1165	lime	2760
lime	195	shale, more wtr	1170	shale	2790
shale	200	sand	1190	shale & lime	2825
lime	215	shale	1195	shale	2830
shale	225	lime	1200	lime	2850
lime	230	shale	1255	shale	2855
shale & shells	265	lime	1275	lime	2860
lime	275	shale	1280	shale	2865
shale	280	lime	1290	lime	2885
lime	290	shale	1300	shale lime	2910
shale	335	lime	1315	lime	2930
lime	355	shale	1325	shale	2940
shale	360	lime	1335	lime	2950
lime	370	shale & shells	1350	shale & shells	2955
red rock	385	shale	1360	shale vari-col.	2964
lime	425	lime	1370	shale	2985
shale	430	shale	1380	lime	2990
lime	520	lime	1385	shale	2994
shale	525	shale	1435	shale vari-col.	
lime	530	lime	1485	& shells	3005
shale	548	shale	1490	shale vari-col.,	
red rock	550	lime	1520	red & yellow	3019
lime	580	shale	1570	lime & chert	3025
red rock	590	lime	1635	chat	3060
lime	625	shale	1675	lime	3200
shale blue	630	lime	1695	(hole filling up	
lime	640	shale	1700	wtr 3095-3107)	
red rock	645	lime	1710	shale	3205
lime	655	shale	1715	lime	3237
shale	670	lime	1730	shale	3245
lime	680	shale	1775	shale blue	3255
shale	690	lime	1800	shale	3270
lime	694	shale	1805	lime	3295
shale	710	lime	1820	shale blk	3315
lime	720	shale	1822	shale	3344
shale	735	lime	1930	2 1/2" BWPH - HW	3347-48
lime	745	shale	1940	lime	3351
shale	755	lime (BW 1975)	1980	shale green	3351.5
lime 2 BW	775	shale	2000	Simpson sand	3398
shale	795	lime	2020	shale (wtr 3353)	3403
lime	810	shale	2035	sand & shale	3418
shale	820	lime	2040	sand & shale green	3430
old blue shale	835	shale	2080	sand	3446
shale	845	shale sdy	2108	chert wh	3449
lime	855	lime	2112	sdv limestone	
shale	870	shale	2199	cherty	3454
lime	955	lime	2205	Total Depth.	
shale	990	shale	2225		
lime	1000	shale & shells	2233		
shale	1025	lime	2285	Top Arbuckle lime	3446