


**WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY**  
 508 East Murdock, Wichita, Kansas

Company- HAL REDMON, INC. ET AL  
 Farm- Harrison No. 1

SEC. 9 T. 28 R. 2E  
 NE NE SW

Total Depth. 3384'  
 Comm. 11-7-54 Comp. 11-16-54  
 Shot or Treated.  
 Contractor.  
 Issued. 12-11-54

County Sedgwick  
 KANSAS



Elevation. 1350 KB

**CASING:**

8 1/4" 104' w/55 sx cem.

Production. Dry

Figures Indicate Bottom of Formations.

All Meas. fr KB		
shale gry	1800-1823	lime light dense finely crystalline cherty 3018
lime gry crystalline	1871	dolomite white finely crystalline 3023
shale gry	1882	lime white dense crystalline cherty 3074
lime gry crystalline	1920	lime light dense finely crystalline 3096
shale jt blk	1924	lime gry dense cherty 3120
lime gry very dense	1926	lime gry dense crystalline 3174
shale blk	1930	lime 3196
lime gry crystalline slightly cherty	1958	shale green -gry 3196
shale gry	1964	lime buff dense 3226
sand light fine micaceous	1970	shale drk 3253
shale gry	2022	detrital lime-shale 3265
sand light fine micaceous	2060	shale brwn-blk 3278
shale gry	2161	sand light fine partly cemented 3312
lime gry crystalline	2230	shale green 3314
shale gry	2504	sand light fine friable 3318
lime gry dense crystalline	2515	shale green-drk 3324
lime light crystalline leached spotted saturation, good odor of oil	2520	sand light fine friable 3330
lime gry dense crystalline	2528	shale green-drk 3345
lime light crystalline oolitic	2535	sand light fine friable 3347
lime light finely crystalline	2547	shale green-drk 3359
lime gry dense crystalline	2570	sand light medium rounded 3362
lime light crystalline leached partly oolitic	2586	shale green 3364
lime gry dense crystalline	2640	chert white 3365
lime gry dense	2688	dolomite buff to gry dense finely crystalline 3384
shale gry to drk	2776	Total Depth
lime gry dense crystalline	2786	TOPS:
shale gry	2848	Heebner 1920
lime gry dense crystalline	2875	Kansas City 2504
shale gry	2898	Marmaton 2688
lime gry dense crystalline	2906	Conglomerate 2951
shale gry	2934	Mississippi 2969
lime buff dense	2941	Kinderhook 3226
sand green fine silty	2944	Simpson 3278
shale drk	2951	Arbuckle 3364
conglomerate various colored shales	2958	
Detrital lime, dolomite, & chert	2969	
chert light to gry translucent	2980	
lime white coarsely crystalline	2998	