

9-28-2E


WELL LOG BUREAU--KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- J. P. GATY
Farm- Thomas No. 2

SEC. 9 T. 28 R. 2E
NW NE SE

Total Depth. 3349
Comm. 2-8-54 Comp. 2-18-54
Shot or Treated.
Contractor. Morrison Drlg. Co., Inc.
Issued. 2-5-55

County Sedgwick
KANSAS



CASING:
5" 3257'

Elevation. 1350 DF

Production. dry

Figures indicate Bottom of Formations.

cement	45 to	75
lime		85
lime & shells		110
shale & lime		130
lime w/shale brks		300
redbed		310
lime & shale		565
shale & lime strks		730
lime & shale		800
shale & lime shells		1290
shale & lime		1840
lime & shale strks		1920
lime		1950
shale & lime		1975
shale & lime strks		2090
lime & shale		2440
shale & lime strks		2502
lime-Kansas City		2572
sandy shale		2587
lime		2608
lime & shale strks		2621
sandy shale & lime		
strks		2655
lime & shale		2971
lime-Top Miss.		2975
cherty lime-Miss.		3055
lime		3090
lime & chert		3137
lime		3150
shale & lime		3175
lime w/shale brks		3221
shale w/lime strks		3250
shale & lime		3256 RTD Corr.
sand		3287
sand & soft, gray-		
green shale		3301
sand		3309
sandy dark gray shale		3319
sand & green shale		3347 1/2
Arbuckle dolomite		3349
Total depth		

Scout Tops:	
Kansas City	2501
Base Kansas City	2703
Kinderhook	3204
Simpson	3255
Arbuckle	3348

Fluid Record Below Pipe
3256-3257 2 BO/d, 25 BW/D
3257-3258 85 BW/D
3261-3270 Hole full of water